
SCALE: 1:100




12.19M WIDE ROAD


GROUND FLOOR PLAN

STAIRS HEAD ROOM

——→ CHEJJA



FIRST, SECOND & THIRD



TYPICAL FLOOR PLAN

Block :A (RESI)

Floor Name	Total Built Up Area		Ded	uctions (Are	Proposed FAR Area (Sq.mt.)	Total FAR Area	Tnmt (No.)			
INdille	(Sq.mt.)	StairCase	Lift	Lift Machine	Void	Ramp	Parking	Resi.	(Sq.mt.)	
Terrace Floor	25.01	22.91	0.00	2.10	0.00	0.00	0.00	0.00	0.00	00
Third Floor	223.37	0.00	2.10	0.00	9.77	0.00	0.00	211.50	211.50	02
Second Floor	223.37	0.00	2.10	0.00	9.77	0.00	0.00	211.50	211.50	02
First Floor	223.37	0.00	2.10	0.00	9.77	0.00	0.00	211.50	211.50	02
Ground Floor	176.04	0.00	2.10	0.00	0.00	0.00	0.00	173.94	173.94	02
Basement Floor	315.06	0.00	0.00	0.00	0.00	100.00	215.06	0.00	0.00	00
Total:	1186.22	22.91	8.40	2.10	29.31	100.00	215.06	808.44	808.44	08
Total Number of Same Blocks	1									
Total:	1186.22	22.91	8.40	2.10	29.31	100.00	215.06	808.44	808.44	08

Required Parking(Table 7a)

Block	ock _{Type}	ype SubUse	Area	Ur	nits		Car				
Name	Турс		Subose	Subuse	Subuse	Subuse	(Sq.mt.)	Reqd.	Prop.	Reqd./Unit	Reqd.
A (RESI)	Residential	Apartment	50 - 225	1	-	1	8	-			
Total: 8											
Parkin	Parking Check (Table 7h)										

Parking Check (Table 7b)

Vehicle Type	Re	eqd.	Achieved		
verlicle Type	No.	Area (Sq.mt.)	No.	Area (Sq.mt.)	
Car	8	110.00	4	55.00	
Two Stack.Car	-	-	4	55.00	
Visitor's Car Parking	1	13.75	0	0.00	
Total Car	9	123.75	8	110.00	
TwoWheeler	-	13.75	0	0.00	
Other Parking	-	-	-	160.06	
Total		137.50		270.06	

Block USE/SUBUSE Details

Block Name	Block Use	Block SubUse	Block Structure	Block Land Use Category
A (RESI)	Residential	Apartment	Bldg upto 11.5 mt. Ht.	R

UnitBUA Table for Block ·A (RESI)

UNITEDIA 1	able for	DIOCK .F	(INLSI)			
FLOOR	Name	UnitBUA Type	UnitBUA Area	Carpet Area	No. of Rooms	No. of Tenement
GROUND FLOOR PLAN	G1	FLAT	99.20	89.35	7	2
	G2	FLAT	53.65	48.09	5	4
TYPICAL - 1, 2& 3 FLOOR PLAN	F1	FLAT	81.89	73.59	10	6
	F2	FLAT	107.65	98.30	9	0
Total:	-	-	721.49	653.12	69	8

ELEVATION

1 28.53 mt. Isng 3.60 mt. High 3.50 mt. Wide Car Ramp

----2.54----

\ 5 & 6

12.19M WIDE ROAD

BASEMENT FLOOR PLAN

FAR &Tenement Details

Block	No. of Same Bldg	Total Built Up Area		Ded	uctions (Are	a in Sq.m	it.)		Proposed FAR Area (Sq.mt.)	Total FAR Area	Tnmt (No.)
	Same blug	(Sq.mt.)	StairCase	Lift	Lift Machine	Void	Ramp	Parking	Resi.	(Sq.mt.)	(140.)
A (RESI)	1	1186.22	22.91	8.40	2.10	29.31	100.00	215.06	808.44	808.44	08
Grand Total:	1	1186.22	22.91	8.40	2.10	29.31	100.00	215.06	808.44	808.44	8.00

SECTION @ A-A

SCHEDULE OF JOINERY:

BLOCK NAME	NAME	LENGTH	HEIGHT	NOS
A (RESI)	D2	0.75	2.10	28
A (RESI)	D1	0.90	2.10	24
A (RESI)	D	0.98	1.80	03
A (RESI)	MD	1.05	2.10	08
A (RESI)	D/W	2.00	1.80	06

//RESIDENTIAL , BUILDING ,

12.19M WIDE ROAD SITE PLAN (SCALE 1:200)

SCHEDULE OF JOINERY:

BLOCK NAME	NAME	LENGTH	HEIGHT	NOS
A (RESI)	V	1.20	1.80	16
A (RESI)	V	1.32	1.80	03
A (RESI)	W	2.00	1.80	51

Approval Condition:

This Plan Sanction is issued subject to the following conditions:

1.Sanction is accorded for the Residential Building at 4021, HAL 2ND STAGE, BANGALORE

a).Consist of 1Basement + 1Ground + 3 only.

2. Sanction is accorded for Residential use only. The use of the building shall not be deviated to any

3.270.06 area reserved for car parking shall not be converted for any other purpose.

4.Development charges towards increasing the capacity of water supply, sanitary and power main has to be paid to BWSSB and BESCOM if any.

5. Necessary ducts for running telephone cables, cubicles at ground level for postal services & space for dumping garbage within the premises shall be provided.

6. The applicant shall INSURE all workmen involved in the construction work against any accident / untoward incidents arising during the time of construction. 7. The applicant shall not stock any building materials / debris on footpath or on roads or on drains.

8. The applicant shall maintain during construction such barricading as considered necessary to prevent dust, debris & other materials endangering the safety of people / structures etc. in & around the site.

9. The applicant shall plant at least two trees in the premises. 10.Permission shall be obtained from forest department for cutting trees before the commencement

The debris shall be removed and transported to near by dumping yard.

11.License and approved plans shall be posted in a conspicuous place of the licensed premises. The building license and the copies of sanctioned plans with specifications shall be mounted on a frame and displayed and they shall be made available during inspections.

12.If any owner / builder contravenes the provisions of Building Bye-laws and rules in force, the Architect / Engineer / Supervisor will be informed by the Authority in the first instance, warned in the second instance and cancel the registration if the same is repeated for the third time. 13. Technical personnel, applicant or owner as the case may be shall strictly adhere to the duties and responsibilities specified in Schedule - IV (Bye-law No. 3.6) under sub section IV-8 (e) to (k).

14. The building shall be constructed under the supervision of a registered structural engineer. 15.On completion of foundation or footings before erection of walls on the foundation and in the case of columnar structure before erecting the columns "COMMENCEMENT CERTIFICATE" shall be obtained. 16. The building should not be occupied without obtaining "OCCUPANCY CERTIFICATE" from the competent authority.

17. Drinking water supplied by BWSSB should not be used for the construction activity of the building.

18. The applicant shall ensure that the Rain Water Harvesting Structures are provided & maintained in good repair for storage of water for non potable purposes or recharge of ground water at all times having a minimum total capacity mentioned in the Bye-law 32(a). 19.If any owner / builder contravenes the provisions of Building Bye-laws and rules in force, the

authority will inform the same to the concerned registered Architect / Engineers / Supervisor in the first instance, warn in the second instance and cancel the registration of the professional if the same is repeated for the third time. 20.The Builder / Contractor / Professional responsible for supervision of work shall not shall not

of the provisions of the Act, Rules, Bye-laws, Zoning Regulations, Standing Orders and Policy Orders of 21.In case of any false information, misrepresentation of facts, or pending court cases, the plan

approval of the authority. They shall explain to the owner s about the risk involved in contravention

materially and structurally deviate the construction from the sanctioned plan, without previous

sanction is deemed cancelled. Special Condition as per Labour Department of Government of Karnataka vide ADDENDUM (HosadaagiHoodike) Letter No. LD/95/LET/2013, dated: 01-04-2013 :

1.Registration of

Applicant / Builder / Owner / Contractor and the construction workers working in the construction site with the "Karnataka Building and Other Construction workers Welfare Board"should be strictly adhered to.

2. The Applicant / Builder / Owner / Contractor should submit the Registration of establishment and list of construction workers engaged at the time of issue of Commencement Certificate. A copy of the same shall also be submitted to the concerned local Engineer in order to inspect the establishment and ensure the registration of establishment and workers working at construction site or work place. 3. The Applicant / Builder / Owner / Contractor shall also inform the changes if any of the list of workers engaged by him.

At any point of time No Applicant / Builder / Owner / Contractor shall


engage a construction worker in his site or work place who is not registered with the "Karnataka Building and Other Construction workers Welfare Board".

1.Accommodation shall be provided for setting up of schools for imparting education to the children o f construction workers in the labour camps / construction sites. 2.List of children of workers shall be furnished by the builder / contractor to the Labour Department

which is mandatory.

3. Employment of child labour in the construction activities strictly prohibited.

4. Obtaining NOC from the Labour Department before commencing the construction work is a must. 5.BBMP will not be responsible for any dispute that may arise in respect of property in question. 6.In case if the documents submitted in respect of property in question is found to be false or fabricated, the plan sanctioned stands cancelled automatically and legal action will be initiated.



The plans are approved in accordance with the acceptance for approval by the Joint Commissioner (EAST) on date: 06/08/2019 | Ip number: BBMP/Ad.Com./FST/0202/19-20 terms and conditions laid down along with this building plan approval.

Validity of this approval is two years from the date of issue.

Name : CHANDAN KUMAR ASWATHAIAH
Designation : Assistant Director Town Planning Organization: BRUHAT BANGALORE
MAHANAGARA PALIKE
Date: 30-Aug-2019 16: 22:46

ASSISTANT DIRECTOR OF TOWN PLANNING (EAST

BHRUHAT BENGALURU MAHANAGARA PALIKE

COLOR INDEX PLOT BOUNDARY ABUTTING ROAD PROPOSED WORK (COVERAGE AREA)

EXISTING (To be retained)

EXISTING (To be demolished)

	(10 be definitioned)					
ADEA STATEMENT (DDMD)	VERSION NO.: 1.0.9					
AREA STATEMENT (BBMP)	VERSION DATE: 01/11/2018	VERSION DATE: 01/11/2018				
PROJECT DETAIL:	•					
Authority: BBMP	Plot Use: Residential	Plot Use: Residential				
Inward_No: BBMP/Ad.Com./EST/0202/19-20	Plot SubUse: Apartment					
Application Type: General	Land Use Zone: Residential (Main)					
Proposal Type: Building Permission	Plot/Sub Plot No.: 4021					
Nature of Sanction: New	Khata No. (As per Khata Extract): 4021	I				
Location: Ring-II	Locality / Street of the property: HAL 2	ND STAGE, BANGALORE				
Building Line Specified as per Z.R: NA						
Zone: East						
Ward: Ward-112						
Planning District: 206-Indiranagar						
AREA DETAILS:	•	SQ.MT.				
AREA OF PLOT (Minimum)	(A)	369.78				
NET AREA OF PLOT	(A-Deductions)	369.78				
COVERAGE CHECK	•	•				
Permissible Coverage area	a (65.00 %)	240.36				
Proposed Coverage Area ((47.61 %)	176.04				
Achieved Net coverage are	ea (47.61 %)	176.04				
Balance coverage area left	t (17.39 %)	64.32				
FAR CHECK						
	zoning regulation 2015 (2.25)	832.01				
	ng I and II (for amalgamated plot -)	0.00				
Allowable TDR Area (60%	•	0.00				
Premium FAR for Plot with	. ,	0.00				
Total Perm. FAR area (2.2	25)	832.01				
Residential FAR (100.00%		808.42				
Proposed FAR Area		808.42				
Achieved Net FAR Area (2	2.19)	808.42				
Balance FAR Area (0.06)		23.59				
BUILT UP AREA CHECK						
Proposed BuiltUp Area		1186.22				
Substructure Area Add in E	BUA (Layout LvI)	0.01				
Achieved BuiltUp Area		1186.23				

Approval Date: 08/06/2019 11:22:14 AM

Payment Details

Sr No.	Challan Number		Amount (INR)		Transaction Number	Payment Date	Remark
1	BBMP/3965/CH/19-20	BBMP/3965/CH/19-20	450	Online	8535340347	06/03/2019 2:34:14 PM	-
	No.		Amount (INR)	Remark			
	1	Scr	utiny Fee	450	-		

OWNER / GPA HOLDER'S SIGNATURE

OWNER'S ADDRESS WITH ID NUMBER & CONTACT NUMBER:

MOHAMMED IMRAN SAIT & MOHAMMED FAIROZ @SITE NO, 4021, HAL 2ND STAGE, BANGALORE. WARD NO. 112, P.I.D NO.72-1-4021.



ARCHITECT/ENGINEER /SUPERVISOR 'S SIGNATURE

MEHBOOB BASHA 03,6TH CROSS, 5TH MAIN, VENKATARANGAPURAM, BANGALORE F-3150/2007-08

PROJECT TITLE:

PROPOSED APARTMENT BUILDING AT SITE NO. 4021, HAL 2ND STAGE, BANGALORE. WARD NO.112, P.I.D NO. 72-1-4021.

DRAWING TITLE:

293490531-08-07-2019 01-10-23\$_\$08072019 ANWAR 50X80 BG3

SHEET NO: