



Block :A1 (SHABEER PASHA)

Floor Name	Total Built Up Area (Sq.mt.)		Deductions (Area in Sq.mt.)				Proposed FAR Area (Sq.mt.)	Total FAR Area	Tnmt (No.)	
	(3q.m.)	StairCase	Lift	Lift Machine	Void	Parking	Resi.	(Sq.mt.)		
Terrace Floor	17.22	13.44	0.00	3.78	0.00	0.00	0.00	0.00	00	
Second Floor	87.55	0.00	2.70	0.00	3.40	0.00	81.45	81.45	01	
First Floor	87.55	0.00	2.70	0.00	3.40	0.00	81.45	81.45	01	
Ground Floor	87.55	0.00	2.70	0.00	3.40	0.00	81.45	81.45	01	
Stilt Floor	80.72	0.00	2.70	0.00	0.00	70.88	0.00	7.14	00	
Total:	360.59	13.44	10.80	3.78	10.20	70.88	244.35	251.49	03	
Total Number of Same Blocks :	1									
Total:	360.59	13.44	10.80	3.78	10.20	70.88	244.35	251.49	03	







SCHEDULE OF JOINERY:


BLOCK NAME	NAME	LENGTH	HEIGHT	NOS			
A1 (SHABEER PASHA)	D2	0.75	2.10	06			
A1 (SHABEER PASHA)	D1	0.91	2.10	13			
A1 (SHABEER PASHA)	D	1.05	2.10	03			
SCHEDULE OF JOINERY:							

BLOCK NAME	NAME	LENGTH	HEIGHT	NOS
A1 (SHABEER PASHA)	v	1.10	0.60	06
A1 (SHABEER PASHA)	W2	1.20	1.80	15
A1 (SHABEER PASHA)	W1	1.50	1.00	03
A1 (SHABEER PASHA)	W	1.80	1.80	15









- LIFT MACHINE ROOM

STAIRCASE HEAD ROOM

-----PARAPET WALL R.C.C.ROOF

- WINDOW

R.C.C.CHEJJA

— WINDOW -R.C.C.ROOF

- WINDOW - 15CM C.C.B WALL -R.C.C.ROOF

LIFT 1.80 X 1.50n TERRACE STAIRCASE 1.80 X 4.45m SOLAR SOLAR 0.H.T. _ **→**2.10

PROPOSED TERRACE FLOOR PLAN

UnitBUA Table for Block :A1 (SHABEER PASHA)

FLOOR	Name	UnitBUA Type	UnitBUA Area	Carpet Area	No. of Rooms	No. of Tenement
GROUND FLOOR PLAN	SPLIT G.F.01	FLAT	81.24	64.55	7	1
TYPICAL - FIRST& SECOND FLOOR PLAN	SPLIT F.F.01	FLAT	81.24	64.55	7	2
Total:	-	-	243.72	193.65	21	3

FAR &Tenement Details

Block	No. of Same Bldg	Total Built Up Area		Deductio	ns (Area in S	Sq.mt.)		Proposed FAR Area (Sq.mt.)	Total FAR Area	Tnmt (No.)
	ounie blug	(Sq.mt.)	StairCase	Lift	Lift Machine	Void	Parking	Resi.	(Sq.mt.)	
A1 (SHABEER PASHA)	1	360.59	13.44	10.80	3.78	10.20	70.88	244.35	251.49	03
Grand Total:	1	360.59	13.44	10.80	3.78	10.20	70.88	244.35	251.49	3.00

Required Parking(Table 7a)

Block	Туре	SubUse	Area	Units		Car		
Name	Type		(Sq.mt.)	Reqd.	Prop.	Reqd./Unit	Reqd.	Prop.
A1 (SHABEER PASHA)	Residential	Plotted Resi development	50 - 225	1	-	1	3	-
	Total :		-	-	-	-	3	3
Parking Check (Table 7b)								

Parking Check (Table 7b)

Vehicle Type	Re	eqd.	Achieved		
	No.	Area (Sq.mt.)	No.	Area (Sq.mt.)	
Car	3	41.25	3	41.25	
Total Car	3	3 41.25		41.25	
Other Parking	-	-	-	29.63	
Total		55.00		70.88	

Approval condition :

This plan sanction is issued subject to the following conditions :

1. Sanction is accorded for the Residential Building at 29, 4th Cross, Manarayanapalya, Bangalore. a).Consist of 1Stilt + 1Ground + 2 only. 2.Sanction is accorded for residential use only. The use of the building shall not be deviated to any other use. 3.70.88 area reserved for car parking shall not be converted for any other purpose. 4.Development charges towards increasing the capacity of water supply, sanitary and power main has to be paid to

BWSSB and BESCOM if any. 5. Necessary ducts for running telephone cables, cubicles at ground level for postal services & space for dumping

garbage within the premises shall be provided. 6.The applicant shall INSURE all workmen involved in the construction work against any accident / untoward incidents arising during the time of construction.

7. The applicant shall not stock any building materials / debris on footpath or on roads or on drains. The debris shall be removed and transported to near by dumping yard.

and other materials endangering the safety of people/ structures in & around the site. 9. The applicant shall plant at least two trees in the premises. 10.Permission shall be obtained from forest department for cutting trees before the commencement of the work. 11.License and approved plans shall be posted in a conspicuous place of the licensed premises. The building license and the copies of sanctioned plans with specifications shall be mounted on a frame and displayed and they shall be made available during inspections.

12.If any owner / builder contravenes the provisions of Building Bye-laws and rules in force, the Architect / Engineer / Supervisor will be informed by the Authority in the first instance, warned in the second instance and cancel the registration if the same is repeated for the third time.

13. Technical personnel, applicant or owner as the case may be shall strictly adhere to the duties and responsibilities specified in Schedule - IV (Bye-law No. 3.6) under sub section IV-8 (e) to (k). 14. The building shall be constructed under the supervision of a registered structural engineer. 15.On completion of foundation or footings before erection of walls on the foundation and in the case of columnar structure before erecting the columns "COMMENCEMENT CERTIFICATE" shall be obtained. 16.Drinking water supplied by BWSSB should not be used for the construction activity of the building. 17. The applicant shall ensure that the Rain Water Harvesting Structures are provided & maintained in good repair for storage of water for non potable purposes or recharge of ground water at all times having a minimum total capacity mentioned in the Bye-law 32(a).

18.If any owner / builder contravenes the provisions of Building Bye-laws and rules in force, the authority will inform the same to the concerned registered Architect / Engineers / Supervisor in the first instance, warn in the second instance and cancel the registration of the professional if the same is repeated for the third time. 19. The Builder / Contractor / Professional responsible for supervision of work shall not shall not materially and structurally deviate the construction from the sanctioned plan, without previous approval of the authority. They shall explain to the owner s about the risk involved in contravention of the provisions of the Act, Rules, Bye-laws, Zoning Regulations, Standing Orders and Policy Orders of the BBMP. 20.In case of any false information, misrepresentation of facts, or pending court cases, the plan sanction is deemed

Special Condition as per Labour Department of Government of Karnataka vide ADDENDUM (HosadaagiHoodike) Letter No. LD/95/LET/2013, dated: 01-04-2013 :

1.Registration of Applicant / Builder / Owner / Contractor and the construction workers working in the construction site with the "Karnataka Building and Other Construction workers Welfare Board"should be strictly adhered to. 2.The Applicant / Builder / Owner / Contractor should submit the Registration of establishment and list of construction workers engaged at the time of issue of Commencement Certificate. A copy of the same shall also be submitted to the concerned local Engineer in order to inspect the establishment and ensure the registration of establishment and workers working at construction site or work place. 3. The Applicant / Builder / Owner / Contractor shall also inform the changes if any of the list of workers engaged by

4.At any point of time No Applicant / Builder / Owner Contractor shall engage a construction worker in his site or work place who is not registered with the "Karnataka Building and Other Construction workers Welfare Board".

1.Accommodation shall be provided for setting up of schools for imparting education to the children of construction workers in the labour camps / construction sites. 2.List of children of workers shall be furnished by the builder contractor to the Labour Department which is

3.Employment of child labour in the construction activities strictly prohibited.

4.Obtaining NOC from the Labour Department before commencing the construction work is a must. 5.88MP will not be responsible for any dispute that may arise in respect of property in question. 6.In case if the documents submitted in respect of property in question is found to be false or fabricated, the plan sanctioned stands cancelled automatically and legal action will be initiated.

SCALE : 1:100

8. The applicant shall maintain during construction such barricading as considered necessary to prevent dust, debris

	COLOF	RINDEX						
	PLOT BC	UNDARY						
	ABUTTIN	IG ROAD						
	PROPOS	PROPOSED WORK (COVERAGE AREA)						
		EXISTING (To be retained)						
		G (To be demolished)						
		VER	SION NO.: 1.0.	9				
AREA ST	ATEMENT (BBMP)		SION DATE: 01					
PROJECT	DETAIL:							
Authority:		Plot	Use: Residentia	l				
Inward_No				d Resi developme	ont			
	.Com./EST/0432/19-20			•	FIL			
	n Type: Suvarna Parvan	•	d Use Zone: Res	sidential (Main)				
Proposal 7	Type: Building Permission		Sub Plot No.: 29					
Nature of	Sanction: New	PID	No. (As per Kha	ta Extract): 96-10)2-29			
Location: I	Ring-II	Loca	ality / Street of th	ne property: 4th c	ross Man	narayan	apalya	
Building Li	ine Specified as per Z.R:	NA						
Zone: Eas	st							
Ward: Wa	rd-022							
Planning D	District: 216-Kaval							
Byrasandr	a							
AREA DE								SQ.MT.
AREA O	F PLOT (Minimum)	(A)						144.63
NET AR	EA OF PLOT	(A-D	eductions)					144.63
COVER	AGE CHECK							
	Permissible Coverage	ge area (75.00 %)						108.47
	Proposed Coverage	Area (55.81 %)						80.72
	Achieved Net covera	age area (55.81 %)						80.72
	Balance coverage a	rea left (19.19 %)						27.75
FAR CH	ECK							
	Permissible F.A.R. a	as per zoning regulation 2	2015(1.75)					253.10
	Additional F.A.R wit	hin Ring I and II (for ama	(for amalgamated plot -)					0.00
	Allowable TDR Area	a (60% of Perm.FAR)						0.00
	Allowable max. F.A.	R Plot within 150 Mt radi	us of Metro stat	ion (-)				0.00
	Total Perm. FAR are	ea(1.75)						253.10
	Residential FAR (97							244.35
	Proposed FAR Area	1						251.49
	Achieved Net FAR A	Area (1.74)						251.49
	Balance FAR Area (0.01)						1.61
BUILT U	IP AREA CHECK	*						
	Proposed BuiltUp A	rea						360.59
	Achieved BuiltUp Ar							360.59
	Date : 07/25/2019	12:28:25 AM			I			
Payment	Details							
Sr No.	Challan Number	Receipt Number	Amount (INR)	Payment Mode	Transa Numbe		Payment Date	Remark
1	BBMP/10837/CH/19-20	BBMP/10837/CH/19-20	1667	Online	877401	8097	07/19/2019 12:28:09 PM	-

	ayment	Details						
	Sr No.	Challan Number	Receipt Number	Amount (INR)	Payment Mode	Transaction Number	Payment Date	Remark
	1	BBMP/10837/CH/19-20	BBMP/10837/CH/19-20	1667	Online	8774018097	07/19/2019 12:28:09 PM	-
		No.		Head			Remark	
		1	Scrutiny Fee			1667	-	
_								

Block USE/SUBUSE Details

The plans are approved in accordance with the acceptance for approval b the Assistant Director of town planning (EAST) on date: 25/07/2019

to terms and conditions laid down along with this building plan approval.

ASSISTANT DIRECTOR OF TOWN PLANNING (EAST

SANCTIONING AUTHORITY : ADTP-EAST

BHRUHAT BENGALURU MAHANAGARA PALIKE

ASSISTANT / JUNIOR ENGINEER / TOWN PLANNER

vide lp number: BBMP/Ad.Com./EST/0432/19-20

Validity of this approval is two years from the date of issue.

Block Name	Block Use	Block SubUse	Block Structure	Block Land Use Category
A1 (SHABEER PASHA)	Residential	Plotted Resi development	Bldg upto 11.5 mt. Ht.	R

OWNER / GPA HOLDER'S SIGNATURE

OWNER'S ADDRESS WITH ID NUMBER & CONTACT NUMBER SHABEER PASHA

No.29, 4th Cross road, Manarayanapalya Ward no.22 Bangalore.

Borg _ subject Signature of the Owner / Applicant

ARCHITECT/ENGINEER

SHEET NO : 1

SUPERVISOR 'S SIGNATURE
_ Rama Subba Reddy
397, Rajesh Nilaya, K G Road Kodicaballi, Sabakar Nagar Post
3CC/BL-3.6/E-3133/07-08
500/BL-3.0/E-3133/07-00

PROJECT TITLE : PROPOSED RESIDENTIAL BUILDING AT NO MANARAYANAPALYA, HEBBAL, BANGALO P.I.D.NO.96-102-29.	, , ,	
DRAWING TITLE : 893711679-19-	07-2019	

DACHA

12-18-01\$_\$SHABEER