



O O O O O O O O

**ELEVATION** 





# Block :AA (BB)

Floor Name	Total Built Up Area		Deductions (Area in Sq.mt.)				Proposed FAR Area (Sq.mt.)	Total FAR Area	Tnmt (No.)
	(Sq.mt.)	StairCase	Lift	Lift Machine	Void	Parking	Resi.	(Sq.mt.)	
Terrace Floor	22.61	20.36	0.00	2.25	0.00	0.00	0.00	0.00	00
Second Floor	133.80	0.00	2.25	0.00	14.68	0.00	116.87	116.87	01
First Floor	133.80	0.00	2.25	0.00	14.68	0.00	116.87	116.87	01
Ground Floor	139.80	0.00	2.25	0.00	0.99	0.00	136.56	136.56	02
Stilt Floor	139.80	0.00	2.25	0.00	0.00	131.33	0.00	6.22	00
Total:	569.81	20.36	9.00	2.25	30.35	131.33	370.30	376.52	04
Total Number of Same Blocks	1								
Total:	569.81	20.36	9.00	2.25	30.35	131.33	370.30	376.52	04

Required Parking(Table 7a)

Block	Type	Cubling	Area	Units		Car		
Name	Туре	SubUse	(Sq.mt.)	Reqd.	Prop.	Reqd./Unit	Reqd.	Prop.
AA (BB)	Residential	Plotted Resi development	50 - 225	1	-	1	4	-
	Total :		-	-	-	-	4	4

Parking Check (Table 7b)

Vehicle Type	Re	qd.	Achieved		
verlicie Type	No.	Area (Sq.mt.)	No.	Area (Sq.mt.)	
Car	4	55.00	4	55.00	
Total Car	4	55.00	4	55.00	
TwoWheeler	-	13.75	0	0.00	
Other Parking	-	-	-	76.33	
Total		68.75		131.33	

FAR &Tenement Details

Block	No. of Same Bldg (2)		Deductions (Area in Sq.mt.)					Proposed FAR Area (Sq.mt.)	Total FAR Area	Tnmt (No.)
	Came Blag	(Sq.mt.)	StairCase	Lift	Lift Machine	Void	Parking	Resi.	(Sq.mt.)	
AA (BB)	1	569.81	20.36	9.00	2.25	30.35	131.33	370.30	376.52	04
Grand Total:	1	569.81	20.36	9.00	2.25	30.35	131.33	370.30	376.52	4.00

## Block USE/SUBUSE Details

Block Name	Block Use	Block SubUse	Block Structure	Block Land Use Category
AA (BB)	Residential	Plotted Resi development	Bldg upto 11.5 mt. Ht.	R

#### Approval Condition:

& around the site.

#### This Plan Sanction is issued subject to the following conditions:

has to be paid to BWSSB and BESCOM if any.

1. Sanction is accorded for the Residential Building at SITE NO- 308, , SITE NO- 308, SY NO- 92/5 , 20th BLOCK, ARKAVATHI LAY OUT, HENNUR VILLAGE, BANGALORE, WARD NO- 24., Bangalore. a).Consist of 1Stilt + 1Ground + 2 only.

2. Sanction is accorded for Residential use only. The use of the building shall not be deviated to any

3.131.33 area reserved for car parking shall not be converted for any other purpose. 4.Development charges towards increasing the capacity of water supply, sanitary and power main

5. Necessary ducts for running telephone cables, cubicles at ground level for postal services & space for dumping garbage within the premises shall be provided.

6. The applicant shall INSURE all workmen involved in the construction work against any accident / untoward incidents arising during the time of construction. 7. The applicant shall not stock any building materials / debris on footpath or on roads or on drains.

The debris shall be removed and transported to near by dumping yard. 8. The applicant shall maintain during construction such barricading as considered necessary to prevent dust, debris & other materials endangering the safety of people / structures etc. in

9. The applicant shall plant at least two trees in the premises. 10.Permission shall be obtained from forest department for cutting trees before the commencement

of the work.

11.License and approved plans shall be posted in a conspicuous place of the licensed premises. The building license and the copies of sanctioned plans with specifications shall be mounted on a frame and displayed and they shall be made available during inspections. 12.If any owner / builder contravenes the provisions of Building Bye-laws and rules in force, the Architect / Engineer / Supervisor will be informed by the Authority in the first instance, warned in the second instance and cancel the registration if the same is repeated for the third time. 13. Technical personnel, applicant or owner as the case may be shall strictly adhere to the duties and responsibilities specified in Schedule - IV (Bye-law No. 3.6) under sub section IV-8 (e) to (k). 14. The building shall be constructed under the supervision of a registered structural engineer.

15.On completion of foundation or footings before erection of walls on the foundation and in the case of columnar structure before erecting the columns "COMMENCEMENT CERTIFICATE" shall be obtained. 16. Drinking water supplied by BWSSB should not be used for the construction activity of the building. 17. The applicant shall ensure that the Rain Water Harvesting Structures are provided & maintained in good repair for storage of water for non potable purposes or recharge of ground water at all times having a minimum total capacity mentioned in the Bye-law 32(a).

18.If any owner / builder contravenes the provisions of Building Bye-laws and rules in force, the authority will inform the same to the concerned registered Architect / Engineers / Supervisor in the first instance, warn in the second instance and cancel the registration of the professional if the same is repeated for the third time. 19. The Builder / Contractor / Professional responsible for supervision of work shall not shall not

approval of the authority. They shall explain to the owner s about the risk involved in contravention of the provisions of the Act, Rules, Bye-laws, Zoning Regulations, Standing Orders and Policy Orders of 20.In case of any false information, misrepresentation of facts, or pending court cases, the plan

materially and structurally deviate the construction from the sanctioned plan, without previous

sanction is deemed cancelled. Special Condition as per Labour Department of Government of Karnataka vide ADDENDUM (HosadaagiHoodike) Letter No. LD/95/LET/2013, dated: 01-04-2013:

#### 1.Registration of Applicant / Builder / Owner / Contractor and the construction workers working in the

construction site with the "Karnataka Building and Other Construction workers Welfare Board"should be strictly adhered to

2. The Applicant / Builder / Owner / Contractor should submit the Registration of establishment and list of construction workers engaged at the time of issue of Commencement Certificate. A copy of the same shall also be submitted to the concerned local Engineer in order to inspect the establishment and ensure the registration of establishment and workers working at construction site or work place. 3. The Applicant / Builder / Owner / Contractor shall also inform the changes if any of the list of

4.At any point of time No Applicant / Builder / Owner / Contractor shall engage a construction worker in his site or work place who is not registered with the "Karnataka Building and Other Construction workers Welfare Board".

1.Accommodation shall be provided for setting up of schools for imparting education to the children o f construction workers in the labour camps / construction sites. 2.List of children of workers shall be furnished by the builder / contractor to the Labour Department which is mandatory.

3. Employment of child labour in the construction activities strictly prohibited. 4. Obtaining NOC from the Labour Department before commencing the construction work is a must. 5.BBMP will not be responsible for any dispute that may arise in respect of property in question. 6.In case if the documents submitted in respect of property in question is found to be false or fabricated, the plan sanctioned stands cancelled automatically and legal action will be initiated.

CROSS SECTION OF RAIN WATER

Percolition trench/pit >

DETAILS OF RAIN WATER HARVESTING STRUCTURES

vide lp number: BBMP/Ad.Com./FST/0796/19-20

Validity of this approval is two years from the date of issue.

1.00M DIA PERCOLATION WELL

CROSS SECTION OF

the Assistant Director of town planning (FAST\_(C)\_) on date:07/11/2019\_

to terms and conditions laid down along with this building plan approval.

Date: 16-Jan-2020 18: 14:41

Name: CHANDAN KUMAR ASWATHAIAH Designation: Assistant Director Town Planning (ADTP)

PERCOLATION PIT/TRENCH

### SCALE: 1:100 **COLOR INDEX** PLOT BOUNDARY ABUTTING ROAD PROPOSED WORK (COVERAGE AREA) EXISTING (To be retained) EXISTING (To be demolished)

THEREOFFI (BBIIII)	VERSION DATE: 01/11/2018				
PROJECT DETAIL:					
Authority: BBMP	Plot Use: Residential				
Inward_No: BBMP/Ad.Com./EST/0796/19-20	Plot SubUse: Plotted Resi development	ot SubUse: Plotted Resi development			
Application Type: Suvarna Parvangi					
Proposal Type: Building Permission	,				
Nature of Sanction: New	City Survey No.: SY NO- 92/5,				
Location: Ring-II	Khata No. (As per Khata Extract): SITE NO- 308,				
Building Line Specified as per Z.R: NA		Locality / Street of the property: SITE NO- 308, SY NO- 92/5, 20th BLOCK, ARKAVATHI LAY OUT, HENNUR VILLAGE, BANGALORE, WARD NO- 24.			
Zone: East (C)					
Ward: Ward - 024 (C)					
Planning District: 217-Kammanahalli					
AREA DETAILS:		SQ.MT.			
AREA OF PLOT (Minimum)	(A)	216.00			
NET AREA OF PLOT	(A-Deductions)	216.00			
COVERAGE CHECK					
Permissible Coverage area (7	75.00 %)	162.00			
Proposed Coverage Area (64	.72 %)	139.80			
Achieved Net coverage area	( 64.72 % )	139.80			
Balance coverage area left (	10.28 % )	22.20			
FAR CHECK					
Permissible F.A.R. as per zor	ning regulation 2015 ( 1.75 )	378.00			
•	and II ( for amalgamated plot - )	0.00			
Allowable TDR Area (60% of	,	0.00			
Premium FAR for Plot within	. , ,	0.00			
Total Perm. FAR area ( 1.75		378.00			
Residential FAR (98.35%)		370.30			
Proposed FAR Area		376.52			
Achieved Net FAR Area ( 1.7	4)	376.52			
Balance FAR Area ( 0.01 )		1.48			
BUILT UP AREA CHECK					
Proposed BuiltUp Area		569.81			
Achieved BuiltUp Area		569.81			

VERSION NO.: 1.0.11

Approval Date: 11/07/2019 1:12:36 PM

## Payment Details

AREA STATEMENT (BBMP)

Sr No.	Challan	Receipt	Amount (INR)	Payment Mode	Transaction	Pavment Date	Remark
Si No.	Number	Number	Amount (iivit)	1 ayment wode	Number	1 ayınıcını Date	Kemark
4	BBMP/20099/CH/19-20	BBMP/20099/CH/19-20	2589.97	Online	9112773335	09/26/2019	
ı	DDIVIP/20099/CH/19-20	DDIVIP/20099/CH/19-20	2509.91	Online	9112773333	7:20:01 PM	-
	No.		Head		Amount (INR)	Remark	
	1	Sc	crutiny Fee		2589 97	_	

## SCHEDULE OF JOINERY:

BLOCK NAME	NAME	LENGTH	HEIGHT	NOS
AA (BB)	D1	0.76	2.10	09
AA (BB)	D1	0.90	2.10	14
AA (BB)	ED	1.05	2.10	04
SCHEDULE	OF JOINERY	<b>′</b> :		
BLOCK NAME	NAME	LENGTH	HEIGHT	NOS

1.00

OWNER / GPA HOLDER'S SIGNATURE

OWNER'S ADDRESS WITH ID NUMBER & CONTACT NUMBER: Mr. FAHIM AFROZ SITE NO- 308, SY NO-92/5, 20th BLOCK, ARKAVATHI LAY

OUT, HENNUR VILLAGE, BANGALORE, WARD NO-



/SUPERVISOR 'S SIGNATURE MALLU MADHUSUDHAN REDDY #2, LEVEL 2, The plans are approved in accordance with the acceptance for approval by SB COMPLEX, NEXT TO IYER SCHOOL, HMT MAIN ROAD, MATHIKERE. BCC/BL-3.6/E-4003/2014-15

ARCHITECT/ENGINEER

THE PLAN OF THE PROPOSED RESIDENTIAL BUILDING AT SITE NO- 308, SY NO- 92/5, 20th BLOCK, ARKAVATHI LAY OUT, HENNUR VILLAGE, BANGALORE, WARD NO- 24.

DRAWING TITLE: ASSISTANT DIRECTOR OF TOWN PLANNING (FAST. (C)

2110786368-14-10-2019 04-49-26\$\_\$12X18

BHRUHAT BENGALURU MAHANAGARA PALIKE

SHEET NO: