

COLOR INDEX

PLOT BOUNDARY ABUTTING ROAD

PROPOSED WORK (COVERAGE AREA)

EXISTING (To be retained) EXISTING (To be demolished)

VERSION NO.: 1.0.11 AREA STATEMENT (BBMP) VERSION DATE: 01/11/2018 PROJECT DETAIL: Authority: BBMP Plot Use: Residential Inward_No: Plot SubUse: Plotted Resi development BBMP/Ad.Com./RJH/1854/19-20 Land Use Zone: Residential (Main) Application Type: Suvarna Parvangi Proposal Type: Building Permission Plot/Sub Plot No.: 50 Nature of Sanction: New Khata No. (As per Khata Extract): 2431/6311/18/50 Location: Ring-III Locality / Street of the property: nagadevenahalli, bangalore Building Line Specified as per Z.R: NA Zone: Rajarajeshwarinagar Ward: Ward-130 Planning District: 301-Kengeri AREA DETAILS: SQ.MT. AREA OF PLOT (Minimum) 111.42 NET AREA OF PLOT (A-Deductions) 111.42 **COVERAGE CHECK** Permissible Coverage area (75.00 %) 83.56 Proposed Coverage Area (62.1 %) 69.19 Achieved Net coverage area (62.1 %) 69.19 Balance coverage area left (12.9 %) 14.37

BUILT UP AREA CHECK Proposed BuiltUp Area 280.46

Approval Date: 01/08/2020 4:15:30 PM

Achieved BuiltUp Area

Payment Details

Sr No.	Challan	Receipt	Amount (INR)	Payment Mode	Transaction	Payment Date	Remark
	Number	Number	Amount (iivit)	r ayment wode	Number	ayment bate	
1	BBMP/31875/CH/19-20	BBMP/31875/CH/19-20	1201.54	Online	9519720105	12/18/2019	
'	DDIVIF/31073/CH/19-20	DDIVIF/31073/CH/13-20	1201.54	Offilite	9319720103	3:53:04 PM	-
	No.		Amount (INR)	Remark			
	1	Scrutiny Fee			1201.54	-	


Block USE/SUBUSE Details

Block Name	Block Use	Block SubUse	Block Structure	Block Land Use Category
A (RESI A)	Residential	Plotted Resi development	Bldg upto 11.5 mt. Ht.	R

OWNER / GPA HOLDER'S SIGNATURE

OWNER'S ADDRESS WITH ID NUMBER & CONTACT NUMBER:

J. NAGARATHNA NO.83/1, 15TH MAIN, VIJAYNAGAR, BANGALORE-560040



0.00

280.46

ARCHITECT/ENGINEER /SUPERVISOR 'S SIGNATURE Harsha d 1ST MAIN, 1ST CROSS

E-4177/2016-17

PROJECT TITLE: PROPOSED RESIDENTIAL BUILDING BBMP KHATA NO: 2431/6311/18/50, SITE NO: 50 NAGADEVENAHALLI, BANGALORE, WARD NO:130, BANGALORE


DRAWING TITLE:


442098908-18-12-2019 02-01-09\$_\$NAGARATHANA

PREDCR 2007V

SHEET NO: 1

.44 X 2.35 KITCHEN 2.75X2.09 LIVING 2.49X3.69 --1.50 -- 1.00 |-- TOILET D2 1.75X1.25 П BED ROOM 2.75X3.35 TOILET STUDY ROOM





Approval Condition:

& around the site.

of the work.

a).Consist of 1Stilt + 1Ground + 2 only.

has to be paid to BWSSB and BESCOM if any.

for dumping garbage within the premises shall be provided.

/ untoward incidents arising during the time of construction.

9. The applicant shall plant at least two trees in the premises.

The debris shall be removed and transported to near by dumping yard.

a frame and displayed and they shall be made available during inspections.

having a minimum total capacity mentioned in the Bye-law 32(a).

(HosadaagiHoodike) Letter No. LD/95/LET/2013, dated: 01-04-2013 :

f construction workers in the labour camps / construction sites.

vide lp number: BBMP/Ad.Com./RJH/1854/19-20

Validity of this approval is two years from the date of issue.

3. Employment of child labour in the construction activities strictly prohibited.

is repeated for the third time.

sanction is deemed cancelled.

Board"should be strictly adhered to

workers engaged by him.

workers Welfare Board".

which is mandatory.

1.Registration of

This Plan Sanction is issued subject to the following conditions

1. Sanction is accorded for the Residential Building at 50, nagadevenahalli, bangalore, Bangalore.

2. Sanction is accorded for Residential use only. The use of the building shall not be deviated to any

4.Development charges towards increasing the capacity of water supply, sanitary and power main

5.Necessary ducts for running telephone cables, cubicles at ground level for postal services & space

6. The applicant shall INSURE all workmen involved in the construction work against any accident

7. The applicant shall not stock any building materials / debris on footpath or on roads or on drains.

8. The applicant shall maintain during construction such barricading as considered necessary to

10.Permission shall be obtained from forest department for cutting trees before the commencement

11.License and approved plans shall be posted in a conspicuous place of the licensed premises. The

building license and the copies of sanctioned plans with specifications shall be mounted on

12.If any owner / builder contravenes the provisions of Building Bye-laws and rules in force, the

Architect / Engineer / Supervisor will be informed by the Authority in the first instance, warned in the second instance and cancel the registration if the same is repeated for the third time.

13.Technical personnel, applicant or owner as the case may be shall strictly adhere to the duties and responsibilities specified in Schedule - IV (Bye-law No. 3.6) under sub section IV-8 (e) to (k). 14. The building shall be constructed under the supervision of a registered structural engineer.

15.On completion of foundation or footings before erection of walls on the foundation and in the case

16. Drinking water supplied by BWSSB should not be used for the construction activity of the building.

17. The applicant shall ensure that the Rain Water Harvesting Structures are provided & maintained in

good repair for storage of water for non potable purposes or recharge of ground water at all times

authority will inform the same to the concerned registered Architect / Engineers / Supervisor in the first instance, warn in the second instance and cancel the registration of the professional if the same

of the provisions of the Act, Rules, Bye-laws, Zoning Regulations, Standing Orders and Policy Orders of

18.If any owner / builder contravenes the provisions of Building Bye-laws and rules in force, the

19. The Builder / Contractor / Professional responsible for supervision of work shall not shall not materially and structurally deviate the construction from the sanctioned plan, without previous approval of the authority. They shall explain to the owner s about the risk involved in contravention

20.In case of any false information, misrepresentation of facts, or pending court cases, the plan

Special Condition as per Labour Department of Government of Karnataka vide ADDENDUM

2. The Applicant / Builder / Owner / Contractor should submit the Registration of establishment and list of construction workers engaged at the time of issue of Commencement Certificate. A copy of the same shall also be submitted to the concerned local Engineer in order to inspect the establishment and ensure the registration of establishment and workers working at construction site or work place. 3. The Applicant / Builder / Owner / Contractor shall also inform the changes if any of the list of

4.At any point of time No Applicant / Builder / Owner / Contractor shall engage a construction worker

in his site or work place who is not registered with the "Karnataka Building and Other Construction

1.Accommodation shall be provided for setting up of schools for imparting education to the children o

2.List of children of workers shall be furnished by the builder / contractor to the Labour Department

4. Obtaining NOC from the Labour Department before commencing the construction work is a must. 5.BBMP will not be responsible for any dispute that may arise in respect of property in question.

6.In case if the documents submitted in respect of property in question is found to be false or fabricated, the plan sanctioned stands cancelled automatically and legal action will be initiated.

The plans are approved in accordance with the acceptance for approval by the Assistant Director of town planning (RR NAGAR) on date:08/01/2020

to terms and conditions laid down along with this building plan approval.

Applicant / Builder / Owner / Contractor and the construction workers working in the construction site with the "Karnataka Building and Other Construction workers Welfare

of columnar structure before erecting the columns "COMMENCEMENT CERTIFICATE" shall be obtaine

prevent dust, debris & other materials endangering the safety of people / structures etc. in


3.62.35 area reserved for car parking shall not be converted for any other purpose.


GROUND FLOOR PLAN

SECTION AT X-X


SECOND FLOOR PLAN

TERRACE FLOOR PLAN





SITE PLAN(SCALE 1:200)



Required Parking(Table 7a)

Block :A (RESI A)

Floor Name	Total Built Up Area (Sq.mt.)	Deductions (Area in Sq.mt.) Area (Sq.m			Proposed FAR Area (Sq.mt.)	Total FAR Area (Sq.mt.)	Tnmt (No.)	
		StairCase	Void	Parking	Resi.			
Terrace Floor	14.71	14.71	0.00	0.00	0.00	0.00	00	
Second Floor	65.52	0.00	3.38	0.00	62.14	62.14	01	
First Floor	65.52	0.00	3.38	0.00	62.14	62.14	01	
Ground Floor	65.52	0.00	3.38	0.00	62.14	62.14	01	
Stilt Floor	69.19	0.00	0.00	62.35	0.00	6.84	00	
Total:	280.46	14.71	10.14	62.35	186.42	193.26	03	
Total Number of Same Blocks :	1							
Total:	280.46	14.71	10.14	62.35	186.42	193.26	03	

ELEVATION

NORTH BY 7.62m WIDE ROAD

STILT FLOOR PLAN

SCHEDULE OF JOINERY:

BLOCK NAME	NAME	LENGTH	HEIGHT	NOS
A (RESI A)	D2	0.75	2.10	06
A (RESI A)	D1	0.90	2.10	09
A (RESI A)	MD	1.10	2.10	03

SCHEDULE OF JOINERY:

BLOCK NAME	NAME	LENGTH	HEIGHT	NOS
A (RESI A)	W6	1.20	1.20	03
A (RESI A)	W6	1.25	1.20	03
A (RESI A)	W1	1.85	1.20	02
A (RESI A)	W1	2.00	1.20	19

•	01	,						
Block	Туре	Cubling	Area	Units		Car		
Name	Type	SubUse	(Sq.mt.)	Reqd.	Prop.	Reqd./Unit	Reqd.	Prop.
(RESI A)	Residential	Plotted Resi development	50 - 225	1		1	3	-
	Total :		1	-	-	-	3	3

Parking Check (Table 7b)

FOUNDATION

AS PERDESIGN

	Re	egd.	Ach	ieved
Vehicle Type	No.	Area (Sq.mt.)	No.	Area (Sq.mt.)
Car	3	41.25	3	41.25
Total Car	3	41.25	3	41.25
TwoWheeler	-	13.75	0	0.00
Other Parking	-	-	-	21.10
Total		55.00		62.35

	Block	No. of Same Bldg	Total Built Up Area (Sq.mt.)	a (Sq.mt.)		rea (Sq.mt.) Deductions (Area in Sq.mt.) FAR Area (Sq.mt.) (Sq.mt.)		Total FAR Area (Sq.mt.)	Tnmt (No.)
				StairCase	Void	Parking	Resi.		
	A (RESI A)	1		14.71	·	62.35	186.42	193.26	03
Г	Grand Total:	1	280.46	14.71	10.14	62.35		193.26	3.00

UnitBUA Table for Block :A (RESI A)

FLOOR	Name	UnitBUA Type	UnitBUA Area	Carpet Area	No. of Rooms	No. of Tenement	
TYPICAL - 1&	TYF-01	DWELLING	61.55	61.55	6	2	
2 FLOOR PLAN	111-01	UNIT	01.55	01.55	Ů		
GROUND	GF-01	DWELLING	61.55	61.55	6	1	
FLOOR PLAN	GI -01	UNIT	01.55	01.55	٥	ı	
Total:	-	-	184.65	184.65	18	3	

BHRUHAT BENGALURU MAHANAGARA PALIKE