


BBMP/Ad.Com./RJH/0377/19-20 Land Use Zone: Residential (Main) Application Type: Suvarna Parvangi Proposal Type: Building Permission Plot/Sub Plot No.: 310 Khata No. (As per Khata Extract): 310/310 Nature of Sanction: New Locality / Street of the property: #310 B.C.M.C LAYOUT, Location: Ring-III RAGHUVANAHALLI VILLAGE Building Line Specified as per Z.R: NA Zone: Rajarajeshwarinagar Ward: Ward-198 Planning District: 301-Kengeri AREA DETAILS: SQ.MT. AREA OF PLOT (Minimum) 111.42 NET AREA OF PLOT (A-Deductions) 111.42 COVERAGE CHECK Permissible Coverage area (75.00 %) 83.56 Proposed Coverage Area (62.29 %) Achieved Net coverage area (62.29 %) 69.40 of columnar structure before erecting the columns "COMMENCEMENT CERTIFICATE" shall be obtained. Balance coverage area left (12.71 %) 14.16 FAR CHECK 17. The applicant shall ensure that the Rain Water Harvesting Structures are provided & maintained in Permissible F.A.R. as per zoning regulation 2015 (1.75) 194.98 Additional F.A.R within Ring I and II (for amalgamated plot -) 0.00 Allowable TDR Area (60% of Perm.FAR) 0.00 Allowable max. F.A.R Plot within 150 Mt radius of Metro station (-) Total Perm. FAR area (1.75) 194.98 Residential FAR (100.00%) Proposed FAR Area 171.43 Achieved Net FAR Area (1.54) 171.43 Balance FAR Area (0.21) 23.55 of the provisions of the Act, Rules, Bye-laws, Zoning Regulations, Standing Orders and Policy Orders of BUILT UP AREA CHECK Proposed BuiltUp Area 220.89 Achieved BuiltUp Area 220.89


SCALE: 1:100

Approval Date: 06/24/2019 11:57:37 AM

Payment Details

Sr No.	Challan Number	Receipt Number	Amount (INR)	Payment Mode	Transaction Number	Payment Date	Remark
1	BBMP/2059/CH/19-20	BBMP/2059/CH/19-20	1181.05	Online	8473360169	05/20/2019 1:20:02 PM	-
	No.		Head		Amount (INR)	Remark	
	1	Scrutiny Fee			1181.05	-	








FRONT ELEVATION

9.14 MTS WIDE ROAD

PROPOSED GROUND FLOOR PLAN







PROPOSED TERRACE FLOOR PLAN

Block :A (A)

Floor Name	Total Built Up Area (Sq.mt.)	Deductions (A	rea in Sq.mt.)	Proposed FAR Area (Sq.mt.)	Total FAR Area	Tnmt (No.)	
	Area (Sq.mt.)	StairCase	Parking	Resi.	(Sq.mt.)		
Terrace Floor	12.69	12.69	0.00	0.00	0.00	00	
Second Floor	69.40	0.00	0.00	69.40	69.40	00	
First Floor	69.40	0.00	0.00	69.40	69.40	01	
Ground Floor	69.40	0.00	36.77	32.63	32.63	01	
Total:	220.89	12.69	36.77	171.43	171.43	02	
Total Number of Same Blocks :	1						
Total:	220.89	12.69	36.77	171.43	171.43	02	

SCHEDULE OF JOINERY:

BLOCK NAME	NAME	LENGTH	HEIGHT	NOS
A (A)	D1	0.76	2.10	07
A (A)	D	0.91	2.10	10

SCHEDULE OF JOINERY:

BLOCK NAME	NAME	LENGTH	HEIGHT	NOS
A (A)	W1	1.43	1.20	01
A (A)	W1	1.50	1.20	33

UnitBUA Table for Block :A (A)

FLOOR	Name	UnitBUA Type	UnitBUA Area	Carpet Area	No. of Rooms	No. of Tenement
GROUND FLOOR PLAN	1	FLAT	32.63	29.21	3	1
FIRST FLOOR PLAN	SPLIT 1	FLAT	138.80	128.87	7	1
SECOND FLOOR PLAN	SPLIT 1	FLAT	0.00	0.00	7	0
Total:	-	-	171.43	158.08	17	2

Block USE/SUBUSE Details

Block Name	Block Use	Block SubUse	Block Structure	Block Land Use Category
A (A)	Residential	Plotted Resi development	Bldg upto 11.5 mt. Ht.	R
Required F	Parking(Table	7a)		

	Block	Type	SubUse	Area	Ur	nits		Car	
	Name	туре		(Sq.mt.)	Reqd.	Prop.	Reqd./Unit	Reqd.	Prop.
	A (A)	Residential	Plotted Resi development	50 - 225	1	-	1	1	-
ı		Total :		_				1	2

Parking Check (Table 7b)

Vehicle Type	R	eqd.	Achieved		
verlicie Type	No.	Area (Sq.mt.)	No.	Area (Sq.mt.)	
Car	1	13.75	2	27.50	
Total Car	1	13.75	2	27.50	
TwoWheeler	-	13.75	0	0.00	
Other Parking	-	-	-	9.27	
Total		27.50		36.77	

FAR &Tenement Details

Block	No. of Same Bldg	Total Built Up Area (Sq.mt.)	Deductions (Area in Sq.mt.)		ns (Area in Sq.mt.)		Tnmt (No.)
			StairCase	Parking	Resi.		
A (A)	1	220.89	12.69	36.77	171.43	171.43	02
Grand Total:	1	220.89	12.69	36.77	171.43	171.43	2.00

The plans are approved in accordance with the acceptance for approval by the Assistant Director of town planning (R_R_NAGAR) on date:24/06/2019 vide lp number:BBMP/Ad.Com./RJH/0377/19-20 to terms and conditions laid down along with this building plan approval. Validity of this approval is two years from the date of issue.

7. The applicant shall not stock any building materials / debris on footpath or on roads or on drains.

8. The applicant shall maintain during construction such barricading as considered necessary to

10.Permission shall be obtained from forest department for cutting trees before the commencement

11.License and approved plans shall be posted in a conspicuous place of the licensed premises. The

building license and the copies of sanctioned plans with specifications shall be mounted on

12.If any owner / builder contravenes the provisions of Building Bye-laws and rules in force, the

the second instance and cancel the registration if the same is repeated for the third time.

responsibilities specified in Schedule - IV (Bye-law No. 3.6) under sub section IV-8 (e) to (k).

14. The building shall be constructed under the supervision of a registered structural engineer.

Architect / Engineer / Supervisor will be informed by the Authority in the first instance, warned in

13. Technical personnel, applicant or owner as the case may be shall strictly adhere to the duties and

15.On completion of foundation or footings before erection of walls on the foundation and in the case

16.Drinking water supplied by BWSSB should not be used for the construction activity of the building.

good repair for storage of water for non potable purposes or recharge of ground water at all times

authority will inform the same to the concerned registered Architect / Engineers / Supervisor in the first instance, warn in the second instance and cancel the registration of the professional if the same

18.If any owner / builder contravenes the provisions of Building Bye-laws and rules in force, the

19. The Builder / Contractor / Professional responsible for supervision of work shall not shall not

materially and structurally deviate the construction from the sanctioned plan, without previous

20.In case of any false information, misrepresentation of facts, or pending court cases, the plan

Special Condition as per Labour Department of Government of Karnataka vide ADDENDUM

Applicant / Builder / Owner / Contractor and the construction workers working in the

construction site with the "Karnataka Building and Other Construction workers Welfare

2. The Applicant / Builder / Owner / Contractor should submit the Registration of establishment and list of construction workers engaged at the time of issue of Commencement Certificate. A copy of the same shall also be submitted to the concerned local Engineer in order to inspect the establishment and ensure the registration of establishment and workers working at construction site or work place.

3. The Applicant / Builder / Owner / Contractor shall also inform the changes if any of the list of

4.At any point of time No Applicant / Builder / Owner / Contractor shall engage a construction worker in his site or work place who is not registered with the "Karnataka Building and Other Construction

1.Accommodation shall be provided for setting up of schools for imparting education to the children o

2.List of children of workers shall be furnished by the builder / contractor to the Labour Department

4. Obtaining NOC from the Labour Department before commencing the construction work is a must.

5.BBMP will not be responsible for any dispute that may arise in respect of property in question.

6.In case if the documents submitted in respect of property in question is found to be false or fabricated, the plan sanctioned stands cancelled automatically and legal action will be initiated.

(HosadaagiHoodike) Letter No. LD/95/LET/2013, dated: 01-04-2013 :

f construction workers in the labour camps / construction sites.

3. Employment of child labour in the construction activities strictly prohibited.

approval of the authority. They shall explain to the owner s about the risk involved in contravention

prevent dust, debris & other materials endangering the safety of people / structures etc. in

The debris shall be removed and transported to near by dumping yard.

a frame and displayed and they shall be made available during inspections.

having a minimum total capacity mentioned in the Bye-law 32(a).

9. The applicant shall plant at least two trees in the premises.

& around the site.

is repeated for the third time.

sanction is deemed cancelled.

Board"should be strictly adhered to

workers engaged by him.

workers Welfare Board".

which is mandatory.

of the work.

ASSISTANT DIRECTOR OF TOWN PLANNING (RAJARAJES) WARINAGAR

BHRUHAT BENGALURU MAHANAGARA PALIKE

OWNER / GPA HOLDER'S SIGNATURE OWNER'S ADDRESS WITH ID NUMBER & CONTACT NUMBER MADAN.B.J #3018 K R ROAD , NEAR UMA MAHESHWARI TEMPLE, B S K 2ND STAGE

ARCHITECT/ENGINEER /SUPERVISOR 'S SIGNATURE SUSHMITHA S #307, 2nd stage,6th nagarabhavi BCC/BL-3.6/4335/2018

PROJECT TITLE : PROPOSED RESIDENTIAL BUILDING FOR MADAN.B.J. ON SITE NO:310, KHATHA NO:310\310,B.C.M.C LAYOUT, RAGHUVANAHALLI VILLAGE BENGALURU WARD NO:198.

DRAWING TITLE	:	1725076120-13-05-2019 05-16-57\$_\$30X40 G2 W198 MADAN B
SHEET NO:	1	J