


SECOND FLOOR PLAN

W


OPEN

TERRACE



FRONT ELEVATION

TERRACE FLOOR PLAN



1.50

9.00 WIDE ROAD

(SCALE 1:200)

PLAN

SECTION ON A' - A'

١					
	BLOCK NAME	NAME	LENGTH	HEIGHT	NOS
	A (RESIDENTIAL)	D2	0.75	2.10	03
	A (RESIDENTIAL)	D1	0.90	2.10	09
ı	A (RESIDENTIAL)	D	1.06	2.10	02

SCHEDULE OF JOINERY:

SCHEDULE OF JOINERY:

BLOCK NAME	NAME	LENGTH	HEIGHT	NOS			
A (RESIDENTIAL)	V	1.20	0.60	03			
A (RESIDENTIAL)	W2		1.20	02			
A (RESIDENTIAL)	W1	1.50	1.20	03			
A (RESIDENTIAL)	W	1.80	1.20	15			
Linitelly Table for Block A (RESIDENTIAL)							

UnitBUA Table for Block :A (RESIDENTIAL)

FLOOR	Name	UnitBUA Type	UnitBUA Area	Carpet Area	No. of Rooms	No. of Tenement
GROUND FLOOR PLAN	SPLIT 1	FLAT	68.22	44.81	6	1
FIRST FLOOR PLAN	SPLIT 2	FLAT	114.04	70.36	5	1
SECOND FLOOR PLAN	SPLIT 2	FLAT	0.00	0.00	2	0
Total:	ı	-	182.26	115.17	13	2

Block : A (RESIDENTIAL)

Floor Name	Total Built Up	' Area (50 mL)		'	Total FAR Area	Tnmt (No.)	
	Area (Sq.mt.)			(Sq.mt.)	`		
Terrace Floor	15.50	15.50	0.00	0.00	0.00	00	
Second Floor	45.82	0.00	0.00	45.82	45.82	00	
First Floor	68.22	0.00	0.00	68.22	68.22	01	
Ground Floor	68.22	0.00	0.00	68.22	68.22	01	
Stilt Floor	68.21	0.00	57.26	0.00	10.95	00	
Total:	265.97	15.50	57.26	182.26	193.21	02	
Total Number of Same Blocks	1						
Total:	265.97	15.50	57.26	182.26		02	

Approval Condition

This Plan Sanction is issued subject to the following conditions:

1. Sanction is accorded for the Residential Building at 72, GIDADA KONENAHALLI, BANGALORE , Bangalore.

a). Consist of 1Stilt + 1Ground + 2 only.

3.57.26 area reserved for car parking shall not be converted for any other purpose.

4. Development charges towards increasing the capacity of water supply, sanitary and power main has to be paid to BWSSB and BESCOM if any.

/ untoward incidents arising during the time of construction. 7. The applicant shall not stock any building materials / debris on footpath or on roads or on drains.

8. The applicant shall maintain during construction such barricading as considered necessary to prevent dust, debris & other materials endangering the safety of people / structures etc. in

10.Permission shall be obtained from forest department for cutting trees before the commencement

a frame and displayed and they shall be made available during inspections. 12.If any owner / builder contravenes the provisions of Building Bye-laws and rules in force, the Architect / Engineer / Supervisor will be informed by the Authority in the first instance, warned in

13. Technical personnel, applicant or owner as the case may be shall strictly adhere to the duties and responsibilities specified in Schedule - IV (Bye-law No. 3.6) under sub section IV-8 (e) to (k). 14. The building shall be constructed under the supervision of a registered structural engineer 15.On completion of foundation or footings before erection of walls on the foundation and in the case of columnar structure before erecting the columns "COMMENCEMENT CERTIFICATE" shall be obtained. 16.Drinking water supplied by BWSSB should not be used for the construction activity of the building. 17. The applicant shall ensure that the Rain Water Harvesting Structures are provided & maintained in good repair for storage of water for non potable purposes or recharge of ground water at all times

18.If any owner / builder contravenes the provisions of Building Bye-laws and rules in force, the authority will inform the same to the concerned registered Architect / Engineers / Supervisor in the first instance, warn in the second instance and cancel the registration of the professional if the same

20.In case of any false information, misrepresentation of facts, or pending court cases, the plan sanction is deemed cancelled.

Special Condition as per Labour Department of Government of Karnataka vide ADDENDUM

Applicant / Builder / Owner / Contractor and the construction workers working in the construction site with the "Karnataka Building and Other Construction workers Welfare Board"should be strictly adhered to

3. The Applicant / Builder / Owner / Contractor shall also inform the changes if any of the list of workers engaged by him.

in his site or work place who is not registered with the "Karnataka Building and Other Construction workers Welfare Board".

Note:

1.Accommodation shall be provided for setting up of schools for imparting education to the children o f construction workers in the labour camps / construction sites. 2.List of children of workers shall be furnished by the builder / contractor to the Labour Department

which is mandatory.

6.In case if the documents submitted in respect of property in question is found to be false or fabricated, the plan sanctioned stands cancelled automatically and legal action will be initiated.

the Assistant Director of town planning (RR NAGAR) on date:16/07/2019 vide lp number: BBMP/Ad.Com./RJH/0632/19-20 to terms and conditions laid down along with this building plan approval. Validity of this approval is two years from the date of issue.

ASSISTANT DIRECTOR OF TOWN PLANNING (RR NAGAR)

BHRUHAT BENGALURU MAHANAGARA PALIKE

2. Sanction is accorded for Residential use only. The use of the building shall not be deviated to any

5. Necessary ducts for running telephone cables, cubicles at ground level for postal services & space for dumping garbage within the premises shall be provided. 6. The applicant shall INSURE all workmen involved in the construction work against any accident

The debris shall be removed and transported to near by dumping yard.

& around the site.

9. The applicant shall plant at least two trees in the premises

11.License and approved plans shall be posted in a conspicuous place of the licensed premises. The building license and the copies of sanctioned plans with specifications shall be mounted on

the second instance and cancel the registration if the same is repeated for the third time.

having a minimum total capacity mentioned in the Bye-law 32(a). is repeated for the third time.

19. The Builder / Contractor / Professional responsible for supervision of work shall not shall not materially and structurally deviate the construction from the sanctioned plan, without previous approval of the authority. They shall explain to the owner s about the risk involved in contravention of the provisions of the Act, Rules, Bye-laws, Zoning Regulations, Standing Orders and Policy Orders of

(HosadaagiHoodike) Letter No. LD/95/LET/2013, dated: 01-04-2013 :

2.The Applicant / Builder / Owner / Contractor should submit the Registration of establishment and list of construction workers engaged at the time of issue of Commencement Certificate. A copy of the same shall also be submitted to the concerned local Engineer in order to inspect the establishment and ensure the registration of establishment and workers working at construction site or work place.

4.At any point of time No Applicant / Builder / Owner / Contractor shall engage a construction worker

3.Employment of child labour in the construction activities strictly prohibited.
4.Obtaining NOC from the Labour Department before commencing the construction work is a must.
5.BBMP will not be responsible for any dispute that may arise in respect of property in question.

The plans are approved in accordance with the acceptance for approval by

EXISTING (To be retained) EXISTING (To be demolished) VERSION NO.: 1.0.9 AREA STATEMENT (BBMP) Plot SubUse: Plotted Resi development BBMP/Ad.Com./RJH/0632/19-20 Land Use Zone: Residential (Main) Application Type: Suvarna Parvangi Proposal Type: Building Permission Plot/Sub Plot No.: 72 Khata No. (As per Khata Extract): 602/470/1/72 Nature of Sanction: New Locality / Street of the property: GIDADA KONENAHALLI,BANGALORE Location: Ring-III Building Line Specified as per Z.R: NA Zone: Rajarajeshwarinagar Ward: Ward-072 Planning District: 301-Kengeri AREA DETAILS: SQ.MT. 111.42 111.42

COLOR INDEX

PLOT BOUNDARY

ABUTTING ROAD

PROPOSED WORK (COVERAGE AREA)

SCALE: 1:100

194.98

182.25

193.21

193.21

1.77

265.97

265.97

,		
AREA OF PLOT (Minimum)	(A)	111.42
NET AREA OF PLOT	(A-Deductions)	111.42
COVERAGE CHECK		
Permissible Coverage area (75.00 %	6)	83.56
Proposed Coverage Area (61.23 %)	68.22	
Achieved Net coverage area (61.23	68.22	
Balance coverage area left (13.77 9	15.34	
FAR CHECK		
Permissible F.A.R. as per zoning re	gulation 2015 (1.75)	194.98
Additional F.A.R within Ring I and II	0.00	
Allowable TDR Area (60% of Perm.	FAR)	0.00
Allowable max. F.A.R Plot within 15	0 Mt radius of Metro station (-)	0.00

Residential FAR (94.33%) Proposed FAR Area Achieved Net FAR Area (1.73) Balance FAR Area (0.02) BUILT UP AREA CHECK

Approval Date: 07/16/2019 1:55:49 PM

Proposed BuiltUp Area

Achieved BuiltUp Area

Payment Details

Sr No.	Challan Number	Receipt Number	Amount (INR)	Payment Mode	Transaction Number	Payment Date	Remark
1	BBMP/8555/CH/19-20	BBMP/8555/CH/19-20	501	Online	8701022123	07/05/2019 1:24:01 PM	-
	No.	Head			Amount (INR)	Remark	
	1	Scrutiny Fee			501	-	·

Block USE/SUBUSE Details

	Block Name	Block Use	Block SubUse	Block Structure	Block Land Use Category		
	A (RESIDENTIAL)	Residential	Plotted Resi development	Bldg upto 11.5 mt. Ht.	R		
Required Parking(Table 7a)							

Block	Туре	SubUse Area (Sq.mt.)	Units		Car			
Name	Турс		(Sq.mt.)	Reqd.	Prop.	Reqd./Unit	Reqd.	Prop.
A (RESIDENTIAL)	Residential	Plotted Resi development	50 - 225	1	-	1	2	-
	Total :		-	-	-	-	2	2

Parking Check (Table 7b)

Vehicle Type	Re	qd.	Achieved		
verlicle Type	No.	No. Area (Sq.mt.)		Area (Sq.mt.)	
Car	2	27.50	2	27.50	
Total Car	2	27.50	2	27.50	
TwoWheeler	-	13.75	0	0.00	
Other Parking	-	-	-	29.76	
Total		41.25		57.26	

FAR &Tenement Details

Block	No. of Same	Total Built Up	Deductions (A	rea in Sq.mt.)		Total FAR	Tnmt (No.)	
DIOCK	Bldg	Area (Sq.mt.)	StairCase	Parking	Resi.	Area (Sq.mt.)	1111111 (140.)	
A (RESIDENTIAL)	1	265.97	15.50	57.26	182.26	193.21	02	
Grand Total:	1	265.97	15.50	57.26	182.26	193.21	2.00	

OWNER / GPA HOLDER'S SIGNATURE OWNER'S ADDRESS WITH ID NUMBER & CONTACT NUMBER: VIJAY KUMAR.B. No:72, Khatha no:602/470/1/72, GIDADA KONENAHALLI, BANGALORE

ARCHITECT/ENGINEER /SUPERVISOR 'S SIGNATURE Rakesh Gowda R 4009/C, 1st A Main Road, B-Block, 2nd Stage, Subramanya Nagar , Bangalore-560021, Mob:6361862394. BCC/BL-3.6/E:3854/2013-14

PROJECT TITLE:

THE PROPOSED RESIDENTIAL BUILDING AT SITE NO:72, KHATHA NO:602/470/1/72, GIDADA KONENAHALLI, BANGALORE, WARD NO: 72.

985995497-04-07-2019 **DRAWING TITLE:** 05-45-03\$_\$VIJAY

SHEET NO: 1

UserDefinedMetric (740.00 x 650.00MM)