

SCALE: 1:100

COLOR INDEX

PLOT BOUNDARY ABUTTING ROAD PROPOSED WORK (COVERAGE AREA) EXISTING (To be retained) EXISTING (To be demolished)



502.99

| ADEA CTATEMENT (DDMD) | VERSION NO.: 1.0.9 | |
|---|--|---------------------|
| AREA STATEMENT (BBMP) | VERSION DATE: 01/11/2018 | |
| PROJECT DETAIL: | • | |
| Authority: BBMP | Plot Use: Residential | |
| Inward_No: BBMP/Ad.Com./RJH/0862/19-20 | Plot SubUse: Plotted Resi developme | ent |
| Application Type: Suvarna Parvangi | Land Use Zone: Residential (Main) | |
| Proposal Type: Building Permission | Plot/Sub Plot No.: 1423 | |
| Nature of Sanction: New | Khata No. (As per Khata Extract): 354 | |
| Location: Ring-III | Locality / Street of the property: #1423 HALAGEVADERAHALLI | B.E.M.L. 5TH STAHE, |
| Building Line Specified as per Z.R: NA | | |
| Zone: Rajarajeshwarinagar | | |
| Ward: Ward-160 | | |
| Planning District: 301-Kengeri | | |
| AREA DETAILS: | | SQ.MT. |
| AREA OF PLOT (Minimum) | (A) | 222.83 |
| NET AREA OF PLOT | (A-Deductions) | 222.83 |
| COVERAGE CHECK | | |
| Permissible Coverage area | | 167.12 |
| Proposed Coverage Area (5 | • | 123.17 |
| Achieved Net coverage area | , | 123.17 |
| Balance coverage area left (| 19.72 %) | 43.95 |
| FAR CHECK | | |
| | oning regulation 2015 (1.75) | 389.95 |
| - | I and II (for amalgamated plot -) | 0.00 |
| Allowable TDR Area (60% o | , | 0.00 |
| Premium FAR for Plot within | 1 () | 0.00 |
| Total Perm. FAR area (1.75 | 389.95 | |
| Residential FAR (96.95%) | 374.9 | |
| Proposed FAR Area | | 386.73 |
| Achieved Net FAR Area (1. | 74) | 386.73 |
| Balance FAR Area (0.01) | | 3.22 |
| BUILT UP AREA CHECK | | |
| Proposed BuiltUp Area | | 503.00 |

Approval Date: 08/20/2019 5:05:59 PM

Achieved BuiltUp Area

Payment Details

| Sr No. | Challan Number | Receipt Number | Amount (INR) | Payment Mode | Transaction Number | Payment Date | Remark |
|--------|---------------------|---------------------|--------------|--------------|-----------------------|---------------------------|--------|
| 1 | BBMP/13048/CH/19-20 | BBMP/13048/CH/19-20 | 2263 | Online | 8853612379 | 08/03/2019 11:30:38 AM | |
| | No. | Head | | | Amount (INR) | Remark | |
| | 1 | Scrutiny Fee | | | 2263 | - | · |

Block USE/SUBUSE Details

| Block Name | Block Use | Block SubUse | Block Structure | Block Land Use Category |
|------------|-------------|-----------------------------|------------------------|----------------------------|
| A (A) | Residential | Plotted Resi development | Bldg upto 11.5 mt. Ht. | R |

Required Parking(Table 7a)


| Block | Type | SubUse | Area | Units | | Car | | |
|-------|-------------|-----------------------------|----------|-------|-------|------------|-------|-------|
| Name | Турс | Subose | (Sq.mt.) | Reqd. | Prop. | Reqd./Unit | Reqd. | Prop. |
| A (A) | Residential | Plotted Resi development | 50 - 225 | 1 | - | 1 | 3 | - |
| | Total : | | - | - | - | - | 3 | 4 |
| | | | 、 | | | | | |

Parking Check (Table 7b)


| Vehicle Type | Re | qa. | Acnieved | | |
|---------------|-----|---------------|----------|---------------|--|
| verlicie Type | No. | Area (Sq.mt.) | No. | Area (Sq.mt.) | |
| Car | 3 | 41.25 | 4 | 55.00 | |
| Total Car | 3 | 41.25 | 4 | 55.00 | |
| TwoWheeler | - | 13.75 | 0 | 0.00 | |
| Other Parking | - | - | - | 22.81 | |
| Total | | 55.00 | | 77.81 | |


FAR &Tenement Details

| Block | No. of Same Bldg | Total Built Up Area | | Deductio | ns (Area in S | Sq.mt.) | | FAR Area (Sq.mt.) | Total FAR Area | Tnmt (No.) | Area other |
|-----------------|---------------------|------------------------|-----------|----------|-----------------|---------|---------|----------------------|-------------------|---------------|------------------|
| | Same blug | (Sq.mt.) | StairCase | Lift | Lift Machine | Void | Parking | Resi. | (Sq.mt.) | (140.) | than Tenement |
| A (A) | 1 | 502.99 | 18.08 | 10.76 | 2.69 | 6.93 | 77.81 | 374.91 | 386.72 | 04 | 19.24 |
| Grand Total: | 1 | 502.99 | 18.08 | 10.76 | 2.69 | 6.93 | 77.81 | 374.91 | 386.72 | 4.00 | 19.24 |
| | | | | | | | | | | | |



PROPOSED GROUND FLOOR PLAN





PROPOSED TERRACE FLOOR PLAN

SECTION ON X-X

Block :A (A)

PROPOSED BASEMENT FLOOR PLAN

| Floor Name | Total Built Up Area | | Deductio | ns (Area in S | Sq.mt.) | | FAR Area (Sq.mt.) | Total FAR Area | Tnmt (No.) | Carpet Area other than |
|--------------------------------------|------------------------|-----------|----------|-----------------|---------|---------|----------------------|-------------------|------------|------------------------------|
| Ivaille | (Sq.mt.) | StairCase | Lift | Lift Machine | Void | Parking | Resi. | (Sq.mt.) | | Tenement |
| Terrace Floor | 20.77 | 18.08 | 0.00 | 2.69 | 0.00 | 0.00 | 0.00 | 0.00 | 00 | 0.00 |
| Third Floor | 113.27 | 0.00 | 2.69 | 0.00 | 2.31 | 0.00 | 108.27 | 108.27 | 01 | 0.00 |
| Second Floor | 113.27 | 0.00 | 2.69 | 0.00 | 2.31 | 0.00 | 108.27 | 108.27 | 01 | 0.00 |
| First Floor | 113.27 | 0.00 | 2.69 | 0.00 | 2.31 | 0.00 | 108.27 | 108.27 | 01 | 0.00 |
| Ground Floor | 123.17 | 0.00 | 2.69 | 0.00 | 0.00 | 77.81 | 30.86 | 42.67 | 01 | 0.00 |
| Basement Floor | 19.24 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 19.24 | 19.24 | 00 | 19.24 |
| Total: | 503.00 | 18.08 | 10.76 | 2.69 | 6.93 | 77.81 | 374.91 | 386.72 | 04 | 19.24 |
| Total Number of Same Blocks | 1 | | | | | | | | | |
| Total: | 503.00 | 18.08 | 10.76 | 2.69 | 6.93 | 77.81 | 374.91 | 386.72 | 04 | 19 |

SCHEDULE OF JOINERY:

| BLOCK NAME | NAME | LENGTH | HEIGHT | NOS | |
|----------------------|------|--------|--------|-----|--|
| A (A) | D | 0.76 | 2.10 | 17 | |
| A (A) | D1 | 0.76 | 2.10 | 03 | |
| A (A) | D | 0.91 | 2.10 | 15 | |
| SCHEDULE OF JOINERY: | | | | | |

LENGTH

W1 1.50 A (A) W1 1.52 W1

UnitBUA Table for Block :A (A)

NAME

| | | | . , | | | |
|---|------|--------------|--------------|-------------|--------------|-----------------|
| FLOOR | Name | UnitBUA Type | UnitBUA Area | Carpet Area | No. of Rooms | No. of Tenement |
| GROUND FLOOR PLAN | 1 | FLAT | 30.86 | 25.49 | 4 | 1 |
| TYPICAL - FIRST, SECOND& THIRD FLOOR PLAN | 2 | FLAT | 108.27 | 93.98 | 8 | 3 |
| Total: | - | - | 355.67 | 307.44 | 28 | 4 |

HEIGHT


1.95

1.95 1.95 NOS

07

44

01



The plans are approved in accordance with the acceptance for approval by the Assistant Director of town planning (RR_NAGAR) on date:20/08/2019 vide lp number: BBMP/Ad.Com./RJH/0862/19-20 to terms and conditions laid down along with this building plan approval. Validity of this approval is two years from the date of issue.

a frame and displayed and they shall be made available during inspections.

having a minimum total capacity mentioned in the Bye-law 32(a).

is repeated for the third time.

sanction is deemed cancelled.

workers engaged by him.

workers Welfare Board".

which is mandatory.

Board"should be strictly adhered to

12.If any owner / builder contravenes the provisions of Building Bye-laws and rules in force, the Architect / Engineer / Supervisor will be informed by the Authority in the first instance, warned in

13. Technical personnel, applicant or owner as the case may be shall strictly adhere to the duties and

the second instance and cancel the registration if the same is repeated for the third time.

responsibilities specified in Schedule - IV (Bye-law No. 3.6) under sub section IV-8 (e) to (k). 14. The building shall be constructed under the supervision of a registered structural engineer. 15.On completion of foundation or footings before erection of walls on the foundation and in the case of columnar structure before erecting the columns "COMMENCEMENT CERTIFICATE" shall be obtained. 16.Drinking water supplied by BWSSB should not be used for the construction activity of the building. 17. The applicant shall ensure that the Rain Water Harvesting Structures are provided & maintained in good repair for storage of water for non potable purposes or recharge of ground water at all times

18.If any owner / builder contravenes the provisions of Building Bye-laws and rules in force, the authority will inform the same to the concerned registered Architect / Engineers / Supervisor in the

19.The Builder / Contractor / Professional responsible for supervision of work shall not shall not materially and structurally deviate the construction from the sanctioned plan, without previous approval of the authority. They shall explain to the owner s about the risk involved in contravention

20.In case of any false information, misrepresentation of facts, or pending court cases, the plan

Applicant / Builder / Owner / Contractor and the construction workers working in the

construction site with the "Karnataka Building and Other Construction workers Welfare

2.The Applicant / Builder / Owner / Contractor should submit the Registration of establishment and

list of construction workers engaged at the time of issue of Commencement Certificate. A copy of the

same shall also be submitted to the concerned local Engineer in order to inspect the establishment and ensure the registration of establishment and workers working at construction site or work place. 3. The Applicant / Builder / Owner / Contractor shall also inform the changes if any of the list of

4.At any point of time No Applicant / Builder / Owner / Contractor shall engage a construction worker in his site or work place who is not registered with the "Karnataka Building and Other Construction

1.Accommodation shall be provided for setting up of schools for imparting education to the children o

2.List of children of workers shall be furnished by the builder / contractor to the Labour Department

4. Obtaining NOC from the Labour Department before commencing the construction work is a must. 5.BBMP will not be responsible for any dispute that may arise in respect of property in question. 6.In case if the documents submitted in respect of property in question is found to be false or fabricated, the plan sanctioned stands cancelled automatically and legal action will be initiated.

(HosadaagiHoodike) Letter No. LD/95/LET/2013, dated: 01-04-2013 :

f construction workers in the labour camps / construction sites.

3.Employment of child labour in the construction activities strictly prohibited.

Special Condition as per Labour Department of Government of Karnataka vide ADDENDUM

first instance, warn in the second instance and cancel the registration of the professional if the same

of the provisions of the Act, Rules, Bye-laws, Zoning Regulations, Standing Orders and Policy Orders of

ASSISTANT DIRECTOR OF TOWN PLANNING (RR NAGAR)

BHRUHAT BENGALURU MAHANAGARA PALIKE

SIGNATURE OWNER'S ADDRESS WITH ID NUMBER & CONTACT NUMBER: K.N.SRINIVASAIAH & K.S.JAYALAKSHMI #33, 2ND CROSS, 3RD MAIN, LK54cmin] BEHIND BALAKRISHNA

RANGAMANDIRA, B.E.M.L 4TH STAGE, 2ND PHASE, R R NAGARA

OWNER / GPA HOLDER'S

ARCHITECT/ENGINEER /SUPERVISOR 'S SIGNATURE SUSHMITHA S #307, 2nd stage,6th block, nagarabhavi BCC/BL-3.6/4335/2010_10

KS. Jag obakshini

PROJECT TITLE : PROPOSED RESIDENTIAL BUILDING ON SITE NO:1423, KHATHA NO:3547\3570\1423\3514, B.E M.L 5TH STAGE, HALAGEVADERAHALLI, R R NAGARA, BENGALURU WARD NO:160.

| DRAWING TITLE : | | 1849558325-02-08-2019 06-54-30\$_\$40X60 BG3 W160 |
|-----------------|---|---|
| SHEET NO: | 1 | SRINIVASAIAH JAYALAKSHMI |

BLOCK NAME