Approval Condition:

sanction is deemed cancelled.

Board"should be strictly adhered to

workers Welfare Board".

which is mandatory.

1.Registration of

19. The Builder / Contractor / Professional responsible for supervision of work shall not shall not

materially and structurally deviate the construction from the sanctioned plan, without previous

20.In case of any false information, misrepresentation of facts, or pending court cases, the plan

Special Condition as per Labour Department of Government of Karnataka vide ADDENDUM

2.The Applicant / Builder / Owner / Contractor should submit the Registration of establishment and list of construction workers engaged at the time of issue of Commencement Certificate. A copy of the same shall also be submitted to the concerned local Engineer in order to inspect the establishment and ensure the registration of establishment and workers working at construction site or work place. 3. The Applicant / Builder / Owner / Contractor shall also inform the changes if any of the list of

4.At any point of time No Applicant / Builder / Owner / Contractor shall engage a construction worker in his site or work place who is not registered with the "Karnataka Building and Other Construction

1.Accommodation shall be provided for setting up of schools for imparting education to the children o

2.List of children of workers shall be furnished by the builder / contractor to the Labour Department

4. Obtaining NOC from the Labour Department before commencing the construction work is a must. 5.BBMP will not be responsible for any dispute that may arise in respect of property in question. 6.In case if the documents submitted in respect of property in question is found to be false or fabricated, the plan sanctioned stands cancelled automatically and legal action will be initiated.

The plans are approved in accordance with the acceptance for approval by the Assistant Director of town planning (RR NAGAR) on date:07/08/2020

to terms and conditions laid down along with this building plan approval.

date of issue of plan and building licence by the competent authority.

This approval of Building plan/ Modified plan is valid for two years from the

ASSISTANT DIRECTOR OF TOWN PLANNING (RR NAGAR)

BHRUHAT BENGALURU MAHANAGARA PALIKE

Applicant / Builder / Owner / Contractor and the construction workers working in the construction site with the "Karnataka Building and Other Construction workers Welfare

(HosadaagiHoodike) Letter No. LD/95/LET/2013, dated: 01-04-2013:

f construction workers in the labour camps / construction sites.

3. Employment of child labour in the construction activities strictly prohibited.

vide Ip number: BBMP/Ad.Com/RJH/ 0447/20-21 subject

approval of the authority. They shall explain to the owner s about the risk involved in contravention

of the provisions of the Act, Rules, Bye-laws, Zoning Regulations, Standing Orders and Policy Orders of

Color Notes

COLOR INDEX PLOT BOUNDARY

ABUTTING ROAD PROPOSED WORK (COVERAGE AREA) EXISTING (To be retained) EXISTING (To be demolished)



201.25

SCALE: 1:100

LAYOUT,NAGARABHAVI,BANGALORE, Bangalore.	AREA STATEMENT (BBMP)	VERSION NO.: 1.0.13	
a).Consist of 1Ground + 2 only.		VERSION DATE: 26/06/2020	
2. Sanction is accorded for Residential use only. The use of the building shall not be deviated to any	PROJECT DETAIL:		
other use.	Authority: BBMP	Plot Use: Residential	
3.28.33 area reserved for car parking shall not be converted for any other purpose. 4.Development charges towards increasing the capacity of water supply, sanitary and power main	Inward_No: BBMP/Ad.Com./RJH/0447/20-21	Plot SubUse: Bungalow	
has to be paid to BWSSB and BESCOM if any. 5.Necessary ducts for running telephone cables, cubicles at ground level for postal services & space	Application Type: Suvarna Parvangi	Land Use Zone: Residential (Main)	
for dumping garbage within the premises shall be provided.	Proposal Type: Building Permission	Plot/Sub Plot No.: 405,	
6. The applicant shall INSURE all workmen involved in the construction work against any accident	Nature of Sanction: NEW	Khata No. (As per Khata Extract): 388/388.	/405/380
/ untoward incidents arising during the time of construction.	Location: RING-II	Locality / Street of the property: NGEF	, 100,000,
7. The applicant shall not stock any building materials / debris on footpath or on roads or on drains.	Essation: Nivo ii	LAYOUT, NAGARABHAVI, BANGALORE	
The debris shall be removed and transported to near by dumping yard.	Building Line Specified as per Z.R: NA		
8. The applicant shall maintain during construction such barricading as considered necessary to	Zone: Rajarajeshwarinagar		
prevent dust, debris & other materials endangering the safety of people / structures etc. in	Ward: Ward-129		
& around the site.	Planning District: 212-Vijayanagar		
9. The applicant shall plant at least two trees in the premises.	AREA DETAILS:		20.147
10.Permission shall be obtained from forest department for cutting trees before the commencement			SQ.MT.
of the work.	AREA OF PLOT (Minimum)	(A)	129.51
11.License and approved plans shall be posted in a conspicuous place of the licensed premises. The	NET AREA OF PLOT	(A-Deductions)	129.51
building license and the copies of sanctioned plans with specifications shall be mounted on	COVERAGE CHECK		
a frame and displayed and they shall be made available during inspections.	Permissible Coverage area (75.00	0 %)	97.13
12.If any owner / builder contravenes the provisions of Building Bye-laws and rules in force, the Architect / Engineer / Supervisor will be informed by the Authority in the first instance, warned in	Proposed Coverage Area (62.41	%)	80.82
the second instance and cancel the registration if the same is repeated for the third time.	Achieved Net coverage area (62	41 %)	80.82
13. Technical personnel, applicant or owner as the case may be shall strictly adhere to the duties and	Balance coverage area left (12.5	9 %)	16.31
responsibilities specified in Schedule - IV (Bye-law No. 3.6) under sub section IV-8 (e) to (k).	FAR CHECK		
14. The building shall be constructed under the supervision of a registered structural engineer.	Permissible F.A.R. as per zoning	regulation 2015 (1.75)	226.64
15.On completion of foundation or footings before erection of walls on the foundation and in the case	Additional F.A.R within Ring I and	, ,	0.00
of columnar structure before erecting the columns "COMMENCEMENT CERTIFICATE" shall be obtained.	Allowable TDR Area (60% of Peri	, ,	0.00
16.Drinking water supplied by BWSSB should not be used for the construction activity of the building.	Premium FAR for Plot within Impa	,	
17. The applicant shall ensure that the Rain Water Harvesting Structures are provided & maintained in		ict zone (-)	0.00
good repair for storage of water for non potable purposes or recharge of ground water at all times	Total Perm. FAR area (1.75)		226.64
having a minimum total capacity mentioned in the Bye-law 32(a).	Residential FAR (100.00%)		160.76
18.If any owner / builder contravenes the provisions of Building Bye-laws and rules in force, the	Proposed FAR Area		160.76
authority will inform the same to the concerned registered Architect / Engineers / Supervisor in the first instance, warn in the second instance and cancel the registration of the professional if the same	Achieved Net FAR Area (1.24)		160.76
is repeated for the third time.	Balance FAR Area (0.51)		65.88
19 The Builder / Contractor / Professional responsible for supervision of work shall not shall not	BUILT UP AREA CHECK		

Approval Date: 08/07/2020 1:27:03 PM


Proposed BuiltUp Area


Achieved BuiltUp Area

Payment Details


Sr No.	Challan	Receipt	Amount (INR)	Payment Mode	Transaction	Payment Date	Remark
SI 140.	Number	Number	7 tillodile (ii vi t)	1 dymont wood	Number	T dymont bato	Remark
1	BBMP/6465/CH/20-21	BBMP/6465/CH/20-21	1322	Online	109895223602	07/06/2020	
'	DDIVIF/0403/G11/20-21	DDIVIF/0403/CI 1/20-2 I	1322	Offilia	103033223002	5:06:11 PM	-
	No.	Head			Amount (INR)	Remark	
	1	S	Scrutiny Fee		1322	-	


ROOM KITCHEN/ 4.19 X 2.52 $\frac{\mathbf{A}}{\triangle}$ DINING 2.50 X 4.17 TOILET 2.55 X 1.50 POOJA 1.20X1.2 PARKING AREA 2.65 X 5.50 4.19 X 6.70 <u>W1</u> <u>W1</u> PERCULATION PIT RECHARGE PIT 9.2 M WIDE ROAD GROUND FLOOR PLAN








SECOND FLOOR PLAN











Block: A (KARIKE)

Floor Name	Total Built Up Area (Sq.mt.)	Deductions (Area in Sq.mt.)		Proposed FAR Area (Sq.mt.)	Total FAR Area (Sq.mt.)	Tnmt (No.)
	Alea (Sq.IIII.)	StairCase	Parking	Resi.	(34.1111.)	
Second Floor	39.60	8.64	0.00	30.96	30.96	00
First Floor	80.82	8.64	0.00	72.18	72.18	00
Ground Floor	80.83	8.64	14.58	57.61	57.61	01
Total:	201.25	25.92	14.58	160.75	160.75	01
Total Number of Same Blocks :	1					
Total:	201.25	25.92	14.58	160.75	160.75	01

equired Parking(Table 7a)										
Block		Cubline Area		Units		Car				
Name	Type SubUse	Subose	(Sq.mt.)	Reqd.	Prop.	Reqd./Unit	Reqd.	Prop.		
A (KARIKE)	Residential	Plotted Resi development	50 - 225	1	-	1	1	-		

Block Structure

Bldg upto 11.5 mt. Ht.

Block SubUse

Plotted Resi

development

Block Land Use

Category

Parking Check (T	able 7b)				
Vehicle Type	R	eqd.	Achieved		
	No.	Area (Sq.mt.)	No.	Area (Sq.mt.)	
Car	1	13.75	1	13.75	
Total Car	1	13.75	1	13.75	
TwoWheeler	-	13.75	0	0.00	
Other Parking	-	-	-	14.58	
Total		27.50		28.33	

FAR &Tenement Details								
Block	No. of Same Bldg	Total Built Up Area (Sq.mt.)	Deductions (Area in Sq.mt.)		Proposed FAR Area (Sq.mt.)	Total FAR Area (Sq.mt.)	Tnmt (No.)	
			StairCase	Parking	Resi.			
A (KARIKE)	1	201.25	25.92	14.58	160.75	160.75	01	
Grand Total:	1	201.25	25.92	14.58	160.75	160.75	1.00	

JnitBUA Table for Block :A (KARIKE)									
FLOOR	Name	UnitBUA Type	UnitBUA Area	Carpet Area	No. of Rooms	No. of Tenement			
GROUND FLOOR PLAN	SPLIT 1	FLAT	186.68	186.68	5	1			
FIRST FLOOR PLAN	SPLIT 1	FLAT	0.00	0.00	7	0			
SECOND FLOOR PLAN	SPLIT 1	FLAT	0.00	0.00	3	0			
Total:	-	-	186.68	186.68	15	1			

Floor Name	Total Built Up	Deductions (Area in Sq.mt.)		Proposed FAR Area (Sq.mt.)	Total FAR Area	Tnmt (No.)
	Area (Sq.mt.)	StairCase	Parking	Resi.	(Sq.mt.)	, ,
Second Floor	39.60	8.64	0.00	30.96	30.96	00
First Floor	80.82	8.64	0.00	72.18	72.18	00
Ground Floor	80.83	8.64	14.58	57.61	57.61	01
Total:	201.25	25.92	14.58	160.75	160.75	01
Total Number of Same Blocks	1					
Total:	201.25	25.92	14.58	160.75	160.75	01

Total:	201.25	25.92	14.58	160.75	160.75	
SCHEDULE OF	JOINERY:					
BLOCK NAME	NAME	L	ENGTH	HEIGHT	NOS	
A (KARIKE)	D1		0.76	2.10	04	
A (KARIKE)	D		0.91	2.10	10	
	•	•	•		•	

SCHEDULE OF JOINERY:								
BLOCK NAME	NAME	LENGTH	HEIGHT	NOS				
A (KARIKE)	V	1.10	1.00	04				
A (KARIKE)	W1	1.80	1.20	22				
A (KARIKE)	W2	2.00	1.00	02				
, ,	.,,_	2.00	1.00	32				

OWNER / GPA HOLDER'S SIGNATURE

OWNER'S ADDRESS WITH ID NUMBER & CONTACT NUMBER: SRI:VENKATESHA PRASAD KARIKE #440/1,FF,7TH "B" MAIN ROAD,4TH BLOCK,JAYANAGAR,

ARCHITECT/ENGINEER /SUPERVISOR 'S SIGNATURE CHANDRASHEKAR D BCC/BL-3-2-3/E-561/1988-89



PROJECT TITLE:

PROPOSED RESIDENTIAL BUILDING ON SITE NO:405, KATHA NO:388/388/405/380, NGEF LAYOUT, NAGARABHAVI, BANGALORE, WARD NO:129.

1017555991-06-07-2020 DRAWING TITLE: 04-02-22\$_\$VENKATESHA PRASAD KARIKE

SHEET NO: 1

Block USE/SUBUSE Details

Residential

Total:

A (KARIKE)