

Block USE/SUBUSE Details

Block Name	Bloc	Block Use Block SubUse Block Structure		Block Land Use Category		e					
A1 (RESIDENTI/ BUILDING)	AL Resid	dential	I Bungalo		Bldg upto 11.5 mt. Ht.		galow Bldg upto 11.5 mt. Ht.			R	
Required	Parking	(Table	7a)								
Block	Type	Cubling	Area		Units			Car			
Name	Туре	SubUse	(Sq.mt.)								
Indille			(04.111.)	Reqd.	Prop.	Reqd./L	Jnit	Reqd.	Prop.		
A1 (RESIDENTIAL BUILDING)	Residential	Bungalow	225.001 - 375	Reqa. 1	Prop.	Reqd./l	Jnit	Reqd. 2	Prop. -		

FRONT ELEVATION

Vehicle Type	Re	qd.	Achieved		
	No.	Area (Sq.mt.)	No.	Area (Sq.mt.)	
Car	2	27.50	3	41.25	
Total Car	2	27.50	3	41.25	
TwoWheeler	-	13.75	0	0.00	
Other Parking	-	-	-	88.56	
Total		41.25		129.81	

FAR &Tenement Details

Block	No. of Same Bldg	Total Built Up Area	It Deductions (Area in Sq.mt.	Sq.mt.)		Proposed FAR Area (Sq.mt.)	Total FAR Area	Tnmt (No.)		
		(Sq.mt.)	StairCase	Lift	Lift Machine	Void	Parking	Resi.	(Sq.mt.)	
A1 (RESIDENTIAL BUILDING)	1	543.96	10.53	9.00	2.25	17.28	129.80	363.35	375.10	01
Grand Total:	1	543.96	10.53	9.00	2.25	17.28	129.80	363.35	375.10	1.00

Block :A1 (RESIDENTIAL BUILDING)


Floor Name	Total Built Up Area	Deductions (Area in Sq.mt.)			Proposed FAR Area (Sq.mt.)	Total FAR Area	Tnmt (No.)		
	(Sq.mt.)	StairCase	Lift	Lift Machine	Void	Parking	Resi.	(Sq.mt.)	
Terrace Floor	12.78	10.53	0.00	2.25	0.00	0.00	0.00	0.00	00
Second Floor	99.78	0.00	2.25	0.00	8.64	0.00	88.89	88.89	00
First Floor	143.80	0.00	2.25	0.00	8.64	0.00	132.91	132.91	00
Ground Floor	143.80	0.00	2.25	0.00	0.00	0.00	141.55	141.55	01
Stilt Floor	143.80	0.00	2.25	0.00	0.00	129.80	0.00	11.75	00
Total:	543.96	10.53	9.00	2.25	17.28	129.80	363.35	375.10	01
Total Number of Same Blocks	1								
Total:	543.96	10.53	9.00	2.25	17.28	129.80	363.35	375.10	01


SCHEDULE OF JOINERY:


BLOCK NAME	NAME	LENGTH	HEIGHT
A1 (RESIDENTIAL BUILDING)	D2	0.75	2.10
A1 (RESIDENTIAL BUILDING)	D1	0.90	2.10
A1 (RESIDENTIAL BUILDING)	D	1.06	2.10
SCHEDULE	OF JOINERY	:	
BLOCK NAME	NAME	LENGTH	HEIGHT
A1 (RESIDENTIAL BUILDING)			1.20
A1 (RESIDENTIAL BUILDING)	A1 (RESIDENTIAL BUILDING) W1		1.20
A1 (RESIDENTIAL BUILDING)	W	1.80	1.20
UnitBUA Ta	ble for Bloo	ck :A1 (RES	SIDENTIAL
FLOOR	Name UnitBUA	Type UnitBUA Area	Carpet Area

FLOOR	Name	UNITBUA Type	UnitBUA Area	Carpet Area
GROUND	SPLIT 1	FLAT	363.35	279.51
FLOOR PLAN	SFLIT I	TLAT	505.55	279.51
FIRST FLOOR	SPLIT 1	FLAT	0.00	0.00
PLAN			0.00	0.00
SECOND	SPLIT 1	FI AT	0.00	0.00
FLOOR PLAN	SFLIT I	TLAT	0.00	0.00
Total:	-	-	363.35	279.51

UserDefinedMetric (840.00 x 780.00MM)







Approval Condition :
This Plan Sanction is issued subject to the following conditions :
1.Sanction is accorded for the Residential Building at 1472 , 3RD BLOCK, SIR M VISHWESHWARAIAH LAYOUT, BANGALORE., Bangalore.
 a).Consist of 1Stilt + 1Ground + 2 only. 2.Sanction is accorded for Residential use only. The use of the building shall not be deviated to any other use.
 3.129.81 area reserved for car parking shall not be converted for any other purpose. 4.Development charges towards increasing the capacity of water supply, sanitary and power main has to be paid to BWSSB and BESCOM if any.
5.Necessary ducts for running telephone cables, cubicles at ground level for postal services & space for dumping garbage within the premises shall be provided.
6. The applicant shall INSURE all workmen involved in the construction work against any accident / untoward incidents arising during the time of construction.
7. The applicant shall not stock any building materials / debris on footpath or on roads or on drains. The debris shall be removed and transported to near by dumping yard.
8. The applicant shall maintain during construction such barricading as considered necessary to prevent dust, debris & other materials endangering the safety of people / structures etc. in & around the site.
9. The applicant shall plant at least two trees in the premises.10. Permission shall be obtained from forest department for cutting trees before the commencement
of the work. 11.License and approved plans shall be posted in a conspicuous place of the licensed premises. The building license and the copies of sanctioned plans with specifications shall be mounted on a frame and displayed and they shall be made available during inspections.
12.If any owner / builder contravenes the provisions of Building Bye-laws and rules in force, the Architect / Engineer / Supervisor will be informed by the Authority in the first instance, warned in the second instance and cancel the registration if the same is repeated for the third time.
 13.Technical personnel, applicant or owner as the case may be shall strictly adhere to the duties and responsibilities specified in Schedule - IV (Bye-law No. 3.6) under sub section IV-8 (e) to (k). 14.The building shall be constructed under the supervision of a registered structural engineer.
15.On completion of foundation or footings before erection of walls on the foundation and in the case of columnar structure before erecting the columns "COMMENCEMENT CERTIFICATE" shall be obtained
16.Drinking water supplied by BWSSB should not be used for the construction activity of the building. 17.The applicant shall ensure that the Rain Water Harvesting Structures are provided & maintained in good repair for storage of water for non potable purposes or recharge of ground water at all times having a minimum total capacity mentioned in the Bye-law 32(a).
18.If any owner / builder contravenes the provisions of Building Bye-laws and rules in force, the authority will inform the same to the concerned registered Architect / Engineers / Supervisor in the first instance, warn in the second instance and cancel the registration of the professional if the same is repeated for the third time.
19. The Builder / Contractor / Professional responsible for supervision of work shall not shall not materially and structurally deviate the construction from the sanctioned plan, without previous approval of the authority. They shall explain to the owner s about the risk involved in contravention
of the provisions of the Act, Rules, Bye-laws, Zoning Regulations, Standing Orders and Policy Orders of the BBMP. 20.In case of any false information, misrepresentation of facts, or pending court cases, the plan sanction is deemed cancelled.
Special Condition as per Labour Department of Government of Karnataka vide ADDENDUM (HosadaagiHoodike) Letter No. LD/95/LET/2013, dated: 01-04-2013 :
1.Registration of
Applicant / Builder / Owner / Contractor and the construction workers working in the construction site with the "Karnataka Building and Other Construction workers Welfare Board"should be strictly adhered to


2. The Applicant / Builder / Owner / Contractor should submit the Registration of establishment and list of construction workers engaged at the time of issue of Commencement Certificate. A copy of the same shall also be submitted to the concerned local Engineer in order to inspect the establishment and ensure the registration of establishment and workers working at construction site or work place. 3. The Applicant / Builder / Owner / Contractor shall also inform the changes if any of the list of workers engaged by him. 4.At any point of time No Applicant / Builder / Owner / Contractor shall engage a construction worker in his site or work place who is not registered with the "Karnataka Building and Other Construction workers Welfare Board".

Note :

1.Accommodation shall be provided for setting up of schools for imparting education to the children o f construction workers in the labour camps / construction sites. 2.List of children of workers shall be furnished by the builder / contractor to the Labour Department which is mandatory. 3.Employment of child labour in the construction activities strictly prohibited.
4.Obtaining NOC from the Labour Department before commencing the construction work is a must.
5.BBMP will not be responsible for any dispute that may arise in respect of property in question. 6.In case if the documents submitted in respect of property in question is found to be false or

The plans are approved in accordance with the acceptance for approval by the Assistant Director of town planning (RR_NAGAR) on date:02/06/2020 vide lp number: BBMP/Ad.Com./RJH/0066/20-21_ to terms and conditions laid down along with this building plan approval. Validity of this approval is two years from the date of issue.

ASSISTANT DIRECTOR OF TOWN PLANNING (RR NAGAR) BHRUHAT BENGALURU MAHANAGARA PALIKE



SITE PLAN (Scale 1:200)

/---1.80---/

				SCALE :	1:10
		COLOR	INDEX		
		PLOT BOU	NDARY		
$-\mathbf{Z}$		ABUTTING	ROAD		
			WORK (COVERAGE AREA)		
			(To be retained)		
			(To be demolished)		
			VERSION NO.: 1.0.11		
AREA	STATEMENT (BBMP)		VERSION DATE: 01/11/2018		
PROJE	ECT DETAIL:		l		
Author	ity: BBMP		Plot Use: Residential		
Inward BBMP	_No: /Ad.Com./RJH/0066/20-	-21	Plot SubUse: Bungalow		
Applic	ation Type: Suvarna Pa	rvangi	Land Use Zone: Residential (Main)		
Propos	al Type: Building Perm	ission	Plot/Sub Plot No.: 1472		
Nature	of Sanction: New		Khata No. (As per Khata Extract): 1472		
Locatio	on: Ring-III		Locality / Street of the property: 3RD BLOCK, SIR M VISHWESHWAF LAYOUT, BANGALORE.	RAIAH	
Buildin	g Line Specified as per	Z.R: NA			
Zone:	Rajarajeshwarinagar				
Ward:	Ward-130				-
Planni	ng District: 301-Kengeri				
AREA	DETAILS:			SQ.MT.	
ARE	A OF PLOT (Minimum)		(A)	216.00)
NET	AREA OF PLOT		(A-Deductions)	216.00)
COV	ERAGE CHECK				
	Permissible Co	verage area (75.0	00 %)	162.00)
	Proposed Cove	rage Area (66.57	7 %)	143.80)
	Achieved Net c	overage area (6	6.57 %)	143.80)
	Balance covera	ge area left (8.4	3 %)	18.20)
FAR	CHECK				
	Permissible F.A	.R. as per zoning	g regulation 2015 (1.75)	378.00)
	Additional F.A.I	R within Ring I ar	nd II (for amalgamated plot -)	0.00)
	Allowable TDR	Area (60% of Pe	erm.FAR)	0.00)
	Premium FAR f	or Plot within Imp	pact Zone (-)	0.00)
	Total Perm. FA	R area (1.75)		378.00)
	Residential FA	R (96.87%)		363.35	;
	Proposed FAR	Area		375.09	
	Achieved Net F	AR Area (1.74)		375.09	
	Balance FAR A			2.9	_
BLIII	T UP AREA CHECK	. ,			1

Approval Date : 06/02/2020 4:06:48 PM

Proposed BuiltUp Area

Achieved BuiltUp Area


Pavment Details

Sr No.	Challan Number	Receipt Number	Amount (INR)	Payment Mode	Transaction Number	Payment Date	Remark
1	BBMP/1579/CH/20-21	BBMP/1579/CH/20-21	2466	Online	10376999889	05/21/2020 11:51:41 AM	-
	No.		Head			Remark	
	1	S	Scrutiny Fee		2466	-	

543.96 543.96

fabricated, the plan sanctioned stands cancelled automatically and legal action will be initiated.

_ subject



DETAILS OF RAIN WATER <u>HARVESTING STRUCTURES</u>

OWNER / GPA HOLDER'S SIGNATURE
OWNER'S ADDRESS WITH ID NUMBER & CONTACT NUMBER : KRISHNA.K.L NO-R-2, UNIVERCITY QUARTERS, UNIVERCITY COMPUS, JNANABHARATHI
and it is the second and a se
ARCHITECT/ENGINEER /SUPERVISOR 'S SIGNATURE RAMESH S #502, SMR ASTRA APARTMENT, 5TH CROSS,GAYATHRINAGAR BCC/BL-3.6/E-4350/18-19
PROJECT TITLE : PLAN SHOWING THE PROPOSED RESIDENTIAL BUILDING AT SITE NO-1472, 3RD BLOCK,SRI M VISHWESHWARAIAH LAYOUT,WARD NO-130, BANGALORE.
DRAWING TITLE : 812901600-02-06-2020 01-47-11\$_\$KRISHNA 12X18 1K
SHEET NO: 1