

**COLOR INDEX** 

PLOT BOUNDARY

ABUTTING ROAD

Approval Date: 06/17/2020 8:10:36 PM

### Payment Details

Sr No.	Challan Number	Receipt Number	Amount (INR)	Payment Mode	Transaction Number	Payment Date	Remark
1	BBMP/3811/CH/20-21	BBMP/3811/CH/20-21	2654	Online	10524272509	06/15/2020 6:07:41 PM	-
	No.		Head		Amount (INR)	Remark	
	1	S	Scrutiny Fee		2654	-	

## Block USE/SUBUSE Details

Block Name	Block Use	Block SubUse	Block Structure	Block Land Use Category
A (N P G)	Residential	Plotted Resi development	Bldg upto 11.5 mt. Ht.	R
D • D		7 - \		


## Required Parking(Table /a)

Block	Type	SubUse	Area	Ur	nits		Car	
Name	туре	Subose	(Sq.mt.)	Reqd.	Prop.	Reqd./Unit	Reqd.	Prop.
A (N P G)	Residential	Plotted Resi development	50 - 225	1	-	1	4	-
	Total :		-	-	-	-	4	4

Parking Check (Table 7b)

Vehicle Type	Re	qd.	Achieved		
venicie rype	No.	Area (Sq.mt.)	No.	Area (Sq.mt.)	
Car	4	55.00	4	55.00	
Total Car	4	55.00	4	55.00	
TwoWheeler	-	13.75	0	0.00	
Other Parking	-	-	-	85.87	
Total		68 75		140.87	

Block	No. of Same Bldg	Total Built Up Area		Deductio	ns (Area in S	Sq.mt.)		Proposed FAR Area (Sq.mt.)	Total FAR Area	Tnmt (No.)
	Cumo Blag	(Sq.mt.)	StairCase	Lift	Lift Machine	Void	Parking	Resi.	(Sq.mt.)	
A (N P G)	1	586.57	20.25	9.00	3.24	23.82	140.87	383.63	389.39	04
Grand Total:	1	586.57	20.25	9.00	3.24	23.82	140.87	383.63	389.39	4.00




Sr No.	Challan Number	Receipt Number	Amount (INR)	Payment Mode	Transaction Number	Payment Date	Remark
1	BBMP/3811/CH/20-21	BBMP/3811/CH/20-21	2654	Online	10524272509	06/15/2020 6:07:41 PM	-
	No.		Head		Amount (INR)	Remark	
	1	S	Scrutiny Fee		2654	-	

•		•	·					
Block	Туре	SubUse	Area	Un	nits		Car	
Name	Турс	Subose	(Sq.mt.)	Reqd.	Prop.	Reqd./Unit	Reqd.	Prop.
A (N P G)	Residential	Plotted Resi development	50 - 225	1	-	1	4	-

Total Car	4	55.00	4	55.00
TwoWheeler	-	13.75	0	0.00
Other Parking	-	-	-	85.87
Total		68.75		140.87
FAR &Tene	ment Detail	S		
				Droposed

Block	No. of Same Bldg	Total Built Up Area		Deductions (Area in Sq.mt.)			FAR Area (Sq.mt.)	Total FAR Area	Tnmt (No.)	
	Jame blug	(Sq.mt.)	StairCase	Lift	Lift Machine	Void	Parking	Resi.	(Sq.mt.)	
A (N P G)	1	586.57	20.25	9.00	3.24	23.82	140.87	383.63	389.39	04
Grand Total:	1	586.57	20.25	9.00	3.24	23.82	140.87	383.63	389.39	4.00
	•									



GROUND FLOOR PLAN (1:100)

2.20M

2.20M

SECTION A-A (1:100)

-ŁIFT M∕C

\_STAIRCASE

---PARAPET WALL

RCC LINTEL

RCC ROOF0.15

BLOCK MASONRY

M THICK 0.15 M THICK SOLID

FOUNDATION TO SUIT SOIL

(1:100)

# Block :A (N P G)

Floor Name	Total Built Up Area (Sq.mt.)		Deductions (Area in Sq.mt.)					Proposed FAR Area Sq.mt.)  Total FAR Area (Sq.mt.)	
	(Sq.IIII.)	StairCase	Lift	Lift Machine	Void	Parking	Resi.	(Sq.IIII.)	
Terrace Floor	23.49	20.25	0.00	3.24	0.00	0.00	0.00	0.00	00
Second Floor	132.66	0.00	2.25	0.00	7.94	0.00	122.47	122.47	01
First Floor	132.66	0.00	2.25	0.00	7.94	0.00	122.47	122.47	01
Ground Floor	148.88	0.00	2.25	0.00	7.94	0.00	138.69	138.69	02
Stilt Floor	148.88	0.00	2.25	0.00	0.00	140.87	0.00	5.76	00
Total:	586.57	20.25	9.00	3.24	23.82	140.87	383.63	389.39	04
Total Number of Same Blocks	1								
Total:	586.57	20.25	9.00	3.24	23.82	140.87	383.63	389.39	04

12.00 M W I D E R O A

2.20M

2.20M

—ŁIFT M∕C

-STAIRCASE

HEAD ROOM

3.00M

2.40M

STILT FLOOR PLAN (1:100)

ELEVATION(1:100)

## SCHEDULE OF JOINERY:


BLOCK NAME	NAME	LENGTH	HEIGHT	NOS
A (N P G)	D2	0.75	2.10	08
A (N P G)	d1	0.90	2.10	06
A (N P G)	D1	0.90	2.10	12
A (N P G)	ED	1.10	2.10	04
A (N P G)	0	3.21	2.10	02

# SCHEDULE OF JOINERY:

BLOCK NAME	NAME	LENGTH	HEIGHT	NOS
A (N P G)	V	0.90	1.50	08
A (N P G)	W1	1.50	2.00	48

UnitBUA Table for Block :A (N P G)

FLOOR	Name	UnitBUA Type	UnitBUA Area	Carpet Area	No. of Rooms	
		FLAT	122.47	92.98	10	2
GROUND	SPLIT 1		60.75	53.31	7	o
FLOOR PLAN	SPLIT 2	FLAT	77.95	52.04	8	2
Total:	-	-	383.63	291.32	35	4



1.00M

RAIN WATER HARVESTING STUCTURE DETAILS

workers Welfare Board".

Approval Condition:

This Plan Sanction is issued subject to the following conditions:

, NELAGADANAHALLI , BENGALURU, Bangalore.

has to be paid to BWSSB and BESCOM if any.

for dumping garbage within the premises shall be provided.

/ untoward incidents arising during the time of construction.

9. The applicant shall plant at least two trees in the premises.

The debris shall be removed and transported to near by dumping yard.

a frame and displayed and they shall be made available during inspections.

having a minimum total capacity mentioned in the Bye-law 32(a).

(HosadaagiHoodike) Letter No. LD/95/LET/2013, dated: 01-04-2013 :

is repeated for the third time.

sanction is deemed cancelled.

Board"should be strictly adhered to

a). Consist of 1Stilt + 1Ground + 2 only.

1. Sanction is accorded for the Residential Building at 278, SREE GRUHALAKSHMI C.S.Ltd

3.140.87 area reserved for car parking shall not be converted for any other purpose.

2.Sanction is accorded for Residential use only. The use of the building shall not be deviated to any

4.Development charges towards increasing the capacity of water supply, sanitary and power main

6. The applicant shall INSURE all workmen involved in the construction work against any accident

7. The applicant shall not stock any building materials / debris on footpath or on roads or on drains.

10.Permission shall be obtained from forest department for cutting trees before the commencement

11.License and approved plans shall be posted in a conspicuous place of the licensed premises. The

13. Technical personnel, applicant or owner as the case may be shall strictly adhere to the duties and responsibilities specified in Schedule - IV (Bye-law No. 3.6) under sub section IV-8 (e) to (k). 14. The building shall be constructed under the supervision of a registered structural engineer. 15.On completion of foundation or footings before erection of walls on the foundation and in the case of columnar structure before erecting the columns "COMMENCEMENT CERTIFICATE" shall be obtained. 16.Drinking water supplied by BWSSB should not be used for the construction activity of the building. 17. The applicant shall ensure that the Rain Water Harvesting Structures are provided & maintained in

good repair for storage of water for non potable purposes or recharge of ground water at all times

authority will inform the same to the concerned registered Architect / Engineers / Supervisor in the first instance, warn in the second instance and cancel the registration of the professional if the same

18.If any owner / builder contravenes the provisions of Building Bye-laws and rules in force, the

19. The Builder / Contractor / Professional responsible for supervision of work shall not shall not

materially and structurally deviate the construction from the sanctioned plan, without previous approval of the authority. They shall explain to the owner s about the risk involved in contravention of the provisions of the Act, Rules, Bye-laws, Zoning Regulations, Standing Orders and Policy Orders of

20.In case of any false information, misrepresentation of facts, or pending court cases, the plan

Special Condition as per Labour Department of Government of Karnataka vide ADDENDUM

2. The Applicant / Builder / Owner / Contractor should submit the Registration of establishment and list of construction workers engaged at the time of issue of Commencement Certificate. A copy of the

same shall also be submitted to the concerned local Engineer in order to inspect the establishment and ensure the registration of establishment and workers working at construction site or work place. 3. The Applicant / Builder / Owner / Contractor shall also inform the changes if any of the list of

4.At any point of time No Applicant / Builder / Owner / Contractor shall engage a construction worker in his site or work place who is not registered with the "Karnataka Building and Other Construction

Applicant / Builder / Owner / Contractor and the construction workers working in the construction site with the "Karnataka Building and Other Construction workers Welfare

building license and the copies of sanctioned plans with specifications shall be mounted on

12.If any owner / builder contravenes the provisions of Building Bye-laws and rules in force, the Architect / Engineer / Supervisor will be informed by the Authority in the first instance, warned in the second instance and cancel the registration if the same is repeated for the third time.

8. The applicant shall maintain during construction such barricading as considered necessary to prevent dust, debris & other materials endangering the safety of people / structures etc. in

5. Necessary ducts for running telephone cables, cubicles at ground level for postal services & space

1.Accommodation shall be provided for setting up of schools for imparting education to the children o f construction workers in the labour camps / construction sites. 2.List of children of workers shall be furnished by the builder / contractor to the Labour Department

3. Employment of child labour in the construction activities strictly prohibited. 4. Obtaining NOC from the Labour Department before commencing the construction work is a must. 5.BBMP will not be responsible for any dispute that may arise in respect of property in question. 6.In case if the documents submitted in respect of property in question is found to be false or fabricated, the plan sanctioned stands cancelled automatically and legal action will be initiated.

The plans are approved in accordance with the acceptance for approval by the Assistant Director of town planning (DASARAHAL) on date:17/06/2020 vide lp number: BBMP/Ad.Com./DSH/0039/20-21 to terms and conditions laid down along with this building plan approval.

Validity of this approval is two years from the date of issue.

ASSISTANT DIRECTOR OF TOWN PLANNING (DASARAHAL).

BHRUHAT BENGALURU MAHANAGARA PALIKE

ARCHITECT/ENGINEER /SUPERVISOR 'S SIGNATURE Ashwath Narayana 185, 3rd Cross, T Dasarahalli,Bengaluru 560057 BCC/BL-3.2.3/E-2071/2001-2002

OWNER / GPA HOLDER'S

OWNER'S ADDRESS WITH ID

SRI. N.P. GOPI. NO 17, 17TH A CROSS,

BNS LAY OUT, MUTHYALANAGARA

NUMBER & CONTACT NUMBER:

SIGNATURE

PROJECT TITLE: PROPOSED RESIDENTIAL BUILDING AT SITE NO 278 ,KHATA NO 409 , SREE GRUHALAKSHMI H.C.S.Ltd , NALLAKADIRENAHALLI , BBMP WARD NO 39, BENGALURU

**DRAWING TITLE:** 1140541474-15-06-2020 01-05-41\$\_\$N SHEET NO: 1