




PROPOSED BASEMENT FLOOR PLAN




PROPOSED GROUND FLOOR PLAN




PROPOSED FIRST FLOOR PLAN




PROPOSED 2 & 3 FLOOR PLAN




ELEVATION



SECTION @ AA



PROPOSED TERRACE FLOOR PLAN



SITE PLAN (SCALE 1:200)

Parking Check (Table 7b)

Vehicle Type	No.	Reqd. Area (Sq.mt.)	Achieved No.	Achieved Area (Sq.mt.)
Car	6	82.50	7	96.25
Visitor's Car Parking	1	13.75	0	0.00
Total Car	7	96.25	7	96.25
TwoWheeler	-	13.75	0	0.00
Other Parking	-	-	-	155.78
Total	-	110.00	-	252.03

FAR & Tenement Details

Block	No. of Same Bldg	Total Built Up Area (Sq.mt.)	Deductions (Area in Sq.mt.)							Proposed A2 (RESIDENTIAL) (Sq.mt.)	Total FAR Area (Sq.mt.)	Tnmt (No.)
			StarCase	Lift	Lift Machine	Duct	Void	Ramp	Parking			
A2 (RESIDENTIAL)	1	1196.77	29.26	11.25	2.25	87.63	126.08	67.23	252.03	621.04	621.04	12
Grand Total	1	1196.77	29.26	11.25	2.25	87.63	126.08	67.23	252.03	621.04	621.04	12.00

Block A2 (RESIDENTIAL)

Floor Name	Total Built Up Area (Sq.mt.)	Deductions (Area in Sq.mt.)							Proposed FAR Area (Sq.mt.)	Total FAR Area (Sq.mt.)	Tnmt (No.)
		StarCase	Lift	Lift Machine	Duct	Void	Ramp	Parking			
Terrace Floor	23.15	20.90	0.00	2.25	0.00	0.00	0.00	0.00	0.00	0.00	00
Third Floor	235.21	0.00	2.25	0.00	29.21	28.85	0.00	0.00	174.90	174.90	03
Second Floor	235.21	0.00	2.25	0.00	29.21	28.85	0.00	0.00	174.90	174.90	03
First Floor	232.97	8.36	2.25	0.00	29.21	18.25	0.00	0.00	174.90	174.90	03
Ground Floor	202.84	0.00	2.25	0.00	0.00	50.13	0.00	54.12	96.34	96.34	03
Basement Floor	267.39	0.00	2.25	0.00	0.00	67.23	197.91	0.00	0.00	0.00	00
Total	1196.77	29.26	11.25	2.25	87.63	126.08	67.23	252.03	621.04	621.04	12

SCHEDULE OF JOINERY:

BLOCK NAME	NAME	LENGTH	HEIGHT	NOS
A2 (RESIDENTIAL)	D2	0.75	2.10	12
A2 (RESIDENTIAL)	D1	0.91	2.10	24
A2 (RESIDENTIAL)	MD	1.05	2.10	12

SCHEDULE OF JOINERY:

BLOCK NAME	NAME	LENGTH	HEIGHT	NOS
A2 (RESIDENTIAL)	V	1.20	1.20	12
A2 (RESIDENTIAL)	W	1.27	1.20	03
A2 (RESIDENTIAL)	W	1.45	1.20	01
A2 (RESIDENTIAL)	W	1.54	1.20	03
A2 (RESIDENTIAL)	W	1.85	1.20	03
A2 (RESIDENTIAL)	W	1.97	1.20	01
A2 (RESIDENTIAL)	W	2.03	1.20	03
A2 (RESIDENTIAL)	W	2.11	1.20	01
A2 (RESIDENTIAL)	W	2.17	1.20	03
A2 (RESIDENTIAL)	W	2.21	1.20	04
A2 (RESIDENTIAL)	W	2.24	1.20	03
A2 (RESIDENTIAL)	W	2.28	1.20	01
A2 (RESIDENTIAL)	W	2.34	1.20	01
A2 (RESIDENTIAL)	W	2.45	1.20	03
A2 (RESIDENTIAL)	W	2.61	1.20	03
A2 (RESIDENTIAL)	W	2.63	1.20	03
A2 (RESIDENTIAL)	W	2.85	1.20	03
A2 (RESIDENTIAL)	W	2.70	1.20	01
A2 (RESIDENTIAL)	W	2.71	1.20	01
A2 (RESIDENTIAL)	W	2.97	1.20	03
A2 (RESIDENTIAL)	W	3.12	1.20	01

- Approval Condition :
- The sanction is accorded for:
 - Consisting of Block - A2 (RESIDENTIAL) Wing - A2-I (RESIDENTIAL) Consisting of BASEMENT, GF+2UF.
 - The sanction is accorded for Apartment A2 (RESIDENTIAL) only. The use of the building shall not deviate to any other use.
 - Car Parking reserved in the plan should not be converted for any other purpose.
 - Development charges towards increasing the capacity of water supply, sanitary and power main has to be paid to BWSSB and BESCOM if any.
 - Necessary ducts for running telephone cables, cubicles at ground level for postal services & space for dumping garbage within the premises shall be provided.
 - The applicant shall construct temporary toilets for the use of construction workers and it should be demolished after the construction.
 - The applicant shall INSURE all workmen involved in the construction work against any accident / untoward incidents arising during the time of construction.
 - The applicant shall not stock any building materials / debris on footpath or on roads or on drains. The debris shall be removed and transported to near by dumping yard.
 - The applicant / builder is prohibited from selling the setback area / open spaces and the common facility areas, which shall be accessible to all the tenants and occupants.
 - The applicant shall provide a space for locating the distribution transformers & associated equipment as per K.E.R.C (E&D) code leaving 3.00 mts. from the building within the premises.
 - The applicant shall provide a separate room preferably 4.50 x 3.65 m in the basement for installation of telecom equipment and also to make provisions for telecom services as per Bye-law No. 25.
 - The applicant shall maintain during construction such barricading as considered necessary to prevent dust, debris & other materials endangering the safety of people / structures etc. in & around the site.
 - Permission shall be obtained from forest department for cutting trees before the commencement of the work.
 - License and approved plans shall be posted in a conspicuous place of the licensed premises. The building license and the copies of sanctioned plans with specifications shall be mounted on a frame and displayed and they shall be kept available for inspection.
 - If any owner / builder contravenes the provisions of Building Bye-laws and rules in force, the Architect / Engineer / Supervisor will be informed by the Authority in the first instance, warned in the second instance and cancel the registration if the same is repeated for the third time.
 - Technical personnel, applicant or owner as the case may be shall strictly adhere to the duties and responsibilities specified in Schedule - IV (Bye-law No. 3.6) under sub section IV (e) (ii) (k).
 - The building shall be constructed under the supervision of a registered structural engineer.
 - On completion of foundation or roofings before erection of walls on the foundation and in the case of columnar structures before erecting the columns "COMMENCEMENT CERTIFICATE" shall be obtained.
 - Construction or reconstruction of the building should be completed before the expiry of five years from the date of issue of license & within one month after its completion shall apply for permission to occupy the building.
 - The building should not be occupied without obtaining "OCCUPANCY CERTIFICATE" from the competent authority.
 - Drinking water supplied by BWSSB should not be used for the construction activity of the building.
 - The applicant shall ensure that the Rain Water Harvesting Structures are provided & maintained in good repair for storage of water for non potable purposes or recharge of ground water at all times having a minimum total capacity mentioned in the Bye-law 32(a).
 - The building shall be designed and constructed adopting the norms prescribed in National Building Code and in the "Criteria for earthquake resistant design of structures" bearing No. IS 1893-2002 published by the Bureau of Indian Standards making the building resistant to earthquake.
 - The applicant should provide solar water heaters as per table 17 of Bye-law No. 29 for the building.
 - Facilities for physically handicapped persons prescribed in schedule XI (Bye laws - 31) of Building bye-laws 2003 shall be ensured.
 - The applicant shall provide at least one common toilet in the ground floor for the use of the visitors / servants / drivers and security men and also entrance shall be approached through a ramp for the Physically Handicapped persons together with the stepped entry.
 - The Occupancy Certificate will be considered only after ensuring that the provisions of conditions vide S.No. 23, 24, 25 & 26 are provided in the building.
 - The applicant shall ensure that no inconvenience is caused to the neighbors in the vicinity of construction and that the construction activities shall stop before 10.00 PM and shall not resume the work earlier than 7.00 AM to avoid hindrance during late hours and early morning hours.
 - Garbage originating from Apartments / Commercial buildings shall be segregated into organic and inorganic waste and should be processed in the Recycling processing unit --- k.g capacity installed at site for re-use / disposal (Applicable to Residential units of 20 and above and 2000 Sq.m and above built up area for Commercial building).
 - The structures with basements shall be designed for structural stability and safety to ensure for soil stabilization during the course of excavation for basements with safe design for retaining walls and super structure for the safety of the structure as well as neighboring property, public roads and footpaths, and besides ensuring safety of workman and general public by erecting safe barricades.

- Registration of Applicant / Builder / Owner / Contractor and the construction workers working in the construction site with the "Karnataka Building and Other Construction workers Welfare Board" should be strictly adhered to.
- The Applicant / Builder / Owner / Contractor should submit the Registration of establishment and list of construction workers engaged at the time of issue of Commencement Certificate. A copy of the same shall also be submitted to the concerned local Engineer in order to inspect the establishment and ensure the registration of establishment and workers working at construction site or work place.
- The Applicant / Builder / Owner / Contractor shall also inform the changes if any of the list of workers engaged by him.
- At any point of time No Applicant / Builder / Owner / Contractor shall engage a construction worker in his site or work place who is not registered with the "Karnataka Building and Other Construction workers Welfare Board".

Note: Earlier plan sanction vide L.P No. _____ is deemed cancelled. The modified plans are approved in accordance with the acceptance for approval by the Joint Commissioner (WEST _____) on date: 20/10/2020 vide lp number: BBMP/Ad.Com./WST/0402/20-21 subject to terms and conditions laid down along with this modified building plan approval.

This approval of Building plan/ Modified plan is valid for two years from the date of issue of plan and building licence by the competent authority.

ASSISTANT DIRECTOR OF TOWN PLANNING (WEST _____)

BHRUHAT BENGALURU MAHANAGARA PALIKE

Balancy Calculations Table

FLOOR	SIZE	AREA	TOTAL AREA
FIRST FLOOR PLAN	0.66 X 4.00 X 1 X 1	2.64	6.64
TYPICAL - 2&3 FLOOR PLAN	1.00 X 2.00 X 2 X 1	4.00	
	0.66 X 4.00 X 1 X 2	5.28	13.28
Total	1.00 X 2.00 X 2 X 2	8.00	19.92

UnitBUA Table for Block A2 (RESIDENTIAL)

FLOOR	Name	UnitBUA Type	UnitBUA Area	Carpel Area	No. of Rooms	No. of Tenement
GROUND FLOOR PLAN	GF-01	FLAT	29.87	27.67	3	3
	GF-02	FLAT	30.39	27.58	3	
	GF-03	FLAT	32.09	28.65	3	
FIRST FLOOR PLAN	FF-01	FLAT	49.09	49.09	4	3
	FF-02	FLAT	49.94	49.94	5	
	FF-03	FLAT	49.84	49.84	4	
TYPICAL - 2&3 FLOOR PLAN	SF-01	FLAT	49.09	49.09	4	6
	SF-02	FLAT	49.94	49.94	5	
	SF-03	FLAT	49.84	49.84	4	
Total:	-	-	538.98	530.54	48	12

Block USE/SUBUSE Details

Block Name	Block Use	Block SubUse	Block Structure	Block Land Use Category
A2 (RESIDENTIAL)	Residential	Apartment	Bldg upto 11.5 mt. HT.	R

Required Parking (Table 7a)

Block Name	Type	SubUse	Area (Sq.mt.)	Reqd.	Prop.	Reqd./Unit	Car Reqd.	Prop.
A2 (RESIDENTIAL)	Residential	Apartment	0-50	2	-	1	6	-
Total:	-	-	-	-	-	-	6	7

Color Notes

COLOR INDEX

AREA STATEMENT (BBMP)

PROJECT DETAIL	VERSION NO. 1.0.15	VERSION DATE: 06/09/2020
Authority: BBMP	Plot Use: Residential	
Inward No: BBMP/Ad.Com./WST/0402/20-21	Plot SubUse: Apartment	
Application Type: General	Land Use Zone: Residential (Main)	
Proposal Type: Building Permission	Plot/Sub Plot No.: 11	
Nature of Sanction: NEW	PID No. (As per Khata Extract): 4-162-11	
Location: RING-II	Locality / Street of the property: "JALADARSHINI LAYOUT" CHIKKAMARANAHALLI VILLAGE, KASABA HOBLI, BANGALORE	
Building Line Specified as per Z/R N/A		
Zone: West		
Ward: Ward-035		
Planning District: 215-Mathikere		

AREA DETAILS

AREA OF PLOT (Minimum)	(A)	SQ.MT.
NET AREA OF PLOT (A-Deductions)	(A)	361.60
COVERED AREA		
Permissible Coverage area (65.00 %)		235.04
Proposed Coverage Area (56.1 %)		202.84
Achieved Net coverage area (56.1 %)		202.84
Balance coverage area left (8.9 %)		32.20
FAR CHECK		
Proposed F.A.R. as per zoning regulation 2015 (1.75)		632.80
Additional F.A.R within Ring Land II (for amalgamated plot -)		0.00
Allowable TDR Area (60% of Perm FAR)		0.00
Premium FAR for Plot within Impact Zone (-)		0.00
Total Perm. FAR area (1.75)		632.80
Residential FAR (100.00%)		621.05
Achieved Net FAR Area (1.72)		621.05
Balance FAR Area (0.03)		11.75
BUILT UP AREA CHECK		
Proposed BuiltUp Area		1196.77
Substructure Area Add in BUA (Layout Lvl)		15.00
Achieved BuiltUp Area		1211.77

Approval Date : 10/20/2020 3:46:58 PM

Payment Details

Sr No.	Challan Number	Receipt Number	Amount (INR)	Payment Mode	Transaction Number	Payment Date	Remark
1	BBMP/11532/CH/20-21	BBMP/11532/CH/20-21	7687	Online	1099693271	08/29/2020 12:32:31 PM	-
	No.		Head		Amount (INR)		Remark
			Scrutiny Fee		7687		

OWNER / GPA HOLDER'S SIGNATURE

OWNER'S ADDRESS WITH ID NUMBER & CONTACT NUMBER : SRI.K.K ASHRAFF #21, KURUBARAHALLI PIPE LINE ROAD, KAVERINAGAR, BASAVESHWARA NAGAR, BANGALORE.

ARCHITECT/ENGINEER /SUPERVISOR'S SIGNATURE

vidya NS #4, Next To Lakshmi Medical, Nagashethihalli Bus Stop, Nagashethihalli, Bangalore /A-2817/2017-18

PROJECT TITLE : PLAN SHOWING THE PROPOSED RESIDENTIAL APARTMENT BUILDING AT SITE NO-11, "JALADARSHINI LAYOUT" CHIKKAMARANAHALLI VILLAGE, KASABA HOBLI, BANGALORE IN WARD NO-35, P ID NO-4-162-11

DRAWING TITLE : 206554066-29-08-2020 10-09-51\$ \$KK ASHRAF B G 3 12K :: A2 (RESIDENTIAL) with BASEMENT, GF+2UF

SHEET NO : 1