

Name	Total Built Up Area (Sq.mt.)		Deductions (Area in Sq.mt.)					Total FAR Area	Tnmt (No.)	
	(04.111.)	StairCase	Lift Lift Machine		Void Parking		Resi.	(Sq.mt.)		
Terrace Floor	23.40	21.60	0.00	1.80	0.00	0.00	0.00	0.00	00	
Second Floor	120.98	35.82	1.80	0.00	14.05	0.00	69.31	69.31	00	
First Floor	120.98	29.67	1.80	0.00	0.00	0.00	89.51	89.51	01	
Ground Floor	120.98	11.17	1.80	0.00	0.00	32.96	75.05	75.05	01	
Total:	386.34	98.26	5.40	1.80	14.05	32.96	233.87	233.87	02	
Total Number of Same Blocks :	1									
Total:	386.34	98.26	5.40	1.80	14.05	32.96	233.87	233.87	02	

SCHEDULE OF	JOINERY:			
BLOCK NAME	NAME	LENGTH	HEIGHT	NOS
A (A)	D2	0.75	2.10	06
A (A)	D1	0.90	2.10	09
A (A)	D	1.06	2.10	02


BLOCK NAME	NAME	LENGTH	HEIGHT	N	
A (A)	W2	1.20	1.20	0	
A (A)	W	2.40	1.20	3	
UnitBUA Table for	Block :A (A)	•			

FLOOR	Name	UnitBUA Type	UnitBUA Area	Carpet Area	No. of Rooms	No. of Tenement
GROUND FLOOR PLAN	gf	FLAT	86.22	80.45	6	1
FIRST FLOOR PLAN	SPLIT tenement	FLAT	224.32	210.64	6	1
SECOND FLOOR PLAN	SPLIT tenement	FLAT	0.00	0.00	5	0
Total:	-	-	310.54	291.09	17	2


Block USE/SUBL	JSE Details			
Block Name	Block Use	Block SubUse	Block Structure	Block Land Use Category
A (A)	Residential	Plotted Resi development	Bldg upto 11.5 mt. Ht.	R

## Required Parking(Table 7a)

	5.	/						
Block	Туре	SubUse	Area	Ur	nits	Car		
Name	Type	Subuse	(Sq.mt.)	Reqd.	Prop.	Reqd./Unit	Reqd.	
A (A)	Residential	Plotted Resi development	50 - 225	1	-	1	2	
	Total :		-	-	-	-	2	
		development	-	-	-	-		




### **PROPOSED SECOND FLOOR PLAN**



### **PROPOSED TERRACE FLOOR** PLAN

Prop.

2



#### Parking Check (Table 7b) Vehicle Type

Vehicle Type		Reqd.	Achieved			
	No.	Area (Sq.mt.)	No.	Area (Sq.mt.)		
Car	2	27.50	2	27.50		
Total Car	2	27.50	2	27.50		
TwoWheeler	-	13.75	0	0.00		
Other Parking	-	-	-	5.46		
Total		41.25	32.96			

### FAR & Tenement Details

Block	No. of Same Bldg			Deductio	ns (Area in S	Proposed FAR Area (Sq.mt.)	Total FAR Area	Tnmt (No.)			
			StairCase	Lift	Lift Machine	Void	Parking	Resi.	(Sq.mt.)		
A (A)	1	386.34	98.26	5.40	1.80	14.05	32.96	233.87	233.87	02	
Grand Total:	1	386.34	98.26	5.40	1.80	14.05	32.96	233.87	233.87	2.00	

### Approval Condition :

This Plan Sanction is issued subject to the following conditions :

### 1. The sanction is accorded for.

a).Consisting of 'Block - A (A) Wing - A-1 (A) Consisting of GF+2UF'. 2. The sanction is accorded for Plotted Resi development A (A) only. The use of the building shall not

deviate to any other use. 3.Car Parking reserved in the plan should not be converted for any other purpose. 4.Development charges towards increasing the capacity of water supply, sanitary and power main

has to be paid to BWSSB and BESCOM if any. 5. Necessary ducts for running telephone cables, cubicles at ground level for postal services & space

for dumping garbage within the premises shall be provided. 6. The applicant shall construct temporary toilets for the use of construction workers and it should be

demolished after the construction. 7. The applicant shall INSURE all workmen involved in the construction work against any accident / untoward incidents arising during the time of construction.

8. The applicant shall not stock any building materials / debris on footpath or on roads or on drains. The debris shall be removed and transported to near by dumping yard. 9. The applicant / builder is prohibited from selling the setback area / open spaces and the common

facility areas, which shall be accessible to all the tenants and occupants. 10. The applicant shall provide a space for locating the distribution transformers & associated equipment as per K.E.R.C (Es& D) code leaving 3.00 mts. from the building within the premises.

11. The applicant shall provide a separate room preferably 4.50 x 3.65 m in the basement for installation of telecom equipment and also to make provisions for telecom services as per Bye-law No. 25

12. The applicant shall maintain during construction such barricading as considered necessary to prevent dust, debris & other materials endangering the safety of people / structures etc. in

& around the site. 13.Permission shall be obtained from forest department for cutting trees before the commencement of the work.

14.License and approved plans shall be posted in a conspicuous place of the licensed premises. The building license and the copies of sanctioned plans with specifications shall be mounted on a frame and displayed and they shall be made available during inspections.

15.If any owner / builder contravenes the provisions of Building Bye-laws and rules in force, the Architect / Engineer / Supervisor will be informed by the Authority in the first instance, warned in the second instance and cancel the registration if the same is repeated for the third time. 16.Technical personnel, applicant or owner as the case may be shall strictly adhere to the duties and responsibilities specified in Schedule - IV (Bye-law No. 3.6) under sub section IV-8 (e) to (k). 17. The building shall be constructed under the supervision of a registered structural engineer. 18.On completion of foundation or footings before erection of walls on the foundation and in the case

of columnar structure before erecting the columns "COMMENCEMENT CERTIFICATE" shall be obtained. 19. Construction or reconstruction of the building should be completed before the expiry of five years from the date of issue of license & within one month after its completion shall apply for permission to occupy the building.

20. The building should not be occupied without obtaining "OCCUPANCY CERTIFICATE" from the competent authority. 21.Drinking water supplied by BWSSB should not be used for the construction activity of the

building 22. The applicant shall ensure that the Rain Water Harvesting Structures are provided & maintained in good repair for storage of water for non potable purposes or recharge of ground water at all

times having a minimum total capacity mentioned in the Bye-law 32(a). 23. The building shall be designed and constructed adopting the norms prescribed in National Building Code and in the "Criteria for earthquake resistant design of structures" bearing No. IS 1893-2002 published by the Bureau of Indian Standards making the building resistant to earthquake. 24. The applicant should provide solar water heaters as per table 17 of Bye-law No. 29 for the buildin

25.Facilities for physically handicapped persons prescribed in schedule XI (Bye laws - 31) of Building bye-laws 2003 shall be ensured.

26. The applicant shall provide at least one common toilet in the ground floor for the use of the visitors / servants / drivers and security men and also entrance shall be approached through a ramp for the Physically Handicapped persons together with the stepped entry.

27. The Occupancy Certificate will be considered only after ensuring that the provisions of conditions vide SI. No. 23, 24, 25 & 26 are provided in the building.

28. The applicant shall ensure that no inconvenience is caused to the neighbors in the vicinity of construction and that the construction activities shall stop before 10.00 PM and shall not resume the work earlier than 7.00 AM to avoid hindrance during late hours and early morning hours.

29.Garbage originating from Apartments / Commercial buildings shall be segregated into organic and inorganic waste and should be processed in the Recycling processing unit ----- k.g capacity installed at site for its re-use / disposal (Applicable for Residential units of 20 and above and

2000 Sqm and above built up area for Commercial building). 30. The structures with basement/s shall be designed for structural stability and safety to ensure for soil stabilization during the course of excavation for basement/s with safe design for retaining walls and super structure for the safety of the structure as well as neighboring property, public roads and

footpaths, and besides ensuring safety of workman and general public by erecting safe barricades. The plans are approved in acc EXISTING BUILDING the Assistant director of town p TO BE DEMOLISHED


> Vide lp number : to terms and conditions laid dow


This approval of Building plan/ date of issue of plan and buildin



# ASSISTANT DIRECTOR BHRUHAT BENGAL







37.The Builder / Contractor / Professional re materially and structurally deviate the const approval of the authority. They shall explain of the provisions of the Act, Rules, Bye-laws the BBMP.

38. The construction or reconstruction of a bu years from date of issue of licence. Before t intimation to BBMP (Sanctioning Authority) Schedule VI. Further, the Owner / Develope footing of walls / columns of the foundation. 39.In case of Development plan, Parks and earmarked and reserved as per Developme 40.All other conditions and conditions mention Development Authority while approving the adhered to

41.The Applicant / Owner / Developer shall a as per solid waste management bye-law 20 42. The applicant/owner/developer shall abid management as per solid waste manageme 43. The Applicant / Owners / Developers sha vehicles

44. The Applicant / Owner / Developer shall Sqm b) minimum of two trees for sites measured Sq.m of the FAR area as part thereof in case unit/development plan.

45.In case of any false information, misrepre sanction is deemed cancelled. 46.Also see, building licence for special con-Special Condition as per Labour Departmen (Hosadaagi Hoodike) Letter No. LD/95/LE1

#### 1.Registration of

Applicant / Builder / Owner / Contractor and construction site with the "Karnataka Buildir Board"should be strictly adhered to

2.The Applicant / Builder / Owner / Contractor list of construction workers engaged at the t same shall also be submitted to the concern and ensure the registration of establishmen 3. The Applicant / Builder / Owner / Contractor

workers engaged by him. 4.At any point of time No Applicant / Builder in his site or work place who is not registered workers Welfare Board".

#### Note :

#### 1.Accommodation shall be provided for setting f construction workers in the labour camps / 2.List of children of workers shall be furnishe which is mandatory.

3.Employment of child labour in the construct 4. Obtaining NOC from the Labour Departme 5.BBMP will not be responsible for any dispu 6.In case if the documents submitted in resp fabricated, the plan sanctioned stands canc

. The certificate should be produced to the Corporation issued once in Two years.									
Iding shall get the building inspected by empaneled ency Department to ensure that the equipment's installed are idavit to that effect shall be submitted to the ery year.			PLOT BOUNDARY ABUTTING ROAD PROPOSED WORK (COVERAGE AREA) EXISTING (To be retained)						
ilding shall obtain clearance certificate from the Electrical pection by the Department regarding working condition of				(To be retained (To be demolis	,				
ate should be produced to the BBMP and shall get the in Two years.	AREA STATI	EMENT (BBMP)	-	VERSION N VERSION D	O.: 1.0.16 ATE: 10/11/2020	)			
building shall conduct two mock - trials in the building her during the summer and assure complete safety in respect of	PROJECT DI Authority: BB			Plot Use: Re	sidential				
esponsible for supervision of work shall not shall not truction from the sanctioned plan, without previous		m./WST/0501/20-21			: Plotted Resi de				
n to the owner s about the risk involved in contravention s, Zoning Regulations, Standing Orders and Policy Orders of		ype: Suvarna Parvar e: Building Permissio	-	Plot/Sub Plot		,			
uilding shall be commenced within a period of two (2) the expiry of two years, the Owner / Developer shall give	Location: RIN			Locality / Str	per Khata Extrac eet of the proper WARA NAGAR.	ty: WEST OF CHO	RD ROAD, 2nd ST	ΓAGE,	
of the intention to start work in the form prescribed in er shall give intimation on completion of the foundation or	Building Line Zone: West	Specified as per Z.R	R: NA	5/10/11/2011					
<ul> <li>Otherwise the plan sanction deemed cancelled.</li> <li>Open Spaces area and Surface Parking area shall be ent Plan issued by the Bangalore Development Authority.</li> </ul>	Ward: Ward- Planning Dist	067 rict: 213-Rajaji Naga	ır						
ioned in the work order issued by the Bangalore Development Plan for the project should be strictly	AREA DETA AREA OF F	ILS: PLOT (Minimum)		(A)				SQ.MT. 196.16	
abide by the collection of solid waste and its segregation	NET AREA COVERAG			(A-Deduction	ns)			196.16	
016. de by sustainable construction and demolition waste ent bye-law 2016.		Permissible Covera Proposed Coverage	e Area (61.68 %	(o)				147.12 120.98	
all make necessary provision to charge electrical		Achieved Net cove Balance coverage	÷ 1					120.98 26.14	
plant one tree for a) sites measuring 180 Sqm up to 240 asuring with more than 240 Sqm. c) One tree for every 240 se of Apartment / group housing / multi-dwelling	FAR CHEC	Permissible F.A.R.		•	· /			343.27	
esentation of facts, or pending court cases, the plan		Additional F.A.R with Allowable TDR Are	a (60% of Perm	n.FAR)	mated plot - )			0.00	
nditions, if any.		Premium FAR for F Total Perm. FAR a	rea ( 1.75 )	ct Zone ( - )				0.00 343.27	
nt of Government of Karnataka vide ADDENDUM 7/2013, dated: 01-04-2013 :		Residential FAR (1 Proposed FAR Are	a					233.87 233.87	
d the construction workers working in the		Achieved Net FAR Balance FAR Area AREA CHECK	, ,					233.87 109.40	
ng and Other Construction workers Welfare		Proposed BuiltUp A Achieved BuiltUp A						386.34 386.34	
tor should submit the Registration of establishment and time of issue of Commencement Certificate. A copy of the rned local Engineer in order to inspect the establishment nt and workers working at construction site or work place. tor shall also inform the changes if any of the list of	Approval D Payment De	ate : 12/30/2020		1		I		300.34	
r / Owner / Contractor shall engage a construction worker ed with the "Karnataka Building and Other Construction		Challan	R	eceipt		Deverent Made	Transaction	Deumant Data	
	Sr No.	Number BBMP/19995/CH/20	N	umber 995/CH/20-21	Amount (INR) 36	Payment Mode Online	Number 11779919551	Payment Date 12/08/2020	Remark
ing up of schools for imparting education to the children o / construction sites.		No. 1			Head Scrutiny Fee		Amount (INR) 36	10:07:12 AM Remark -	
ed by the builder / contractor to the Labour Department ction activities strictly prohibited.									
celled automatically and legal action will be initiated. cordance with the acceptance for approv- lanning ( <u>WEST</u> ) on date: <u>30/12/2</u> <u>BMP/AD.COM./WST/0501/20-21</u> sul- wn along with this building plan approv- Modified plan is valid for two years from ng licence by the competent authority. Name: VEERESH ALADAKATTI Designation : Assistant Director Town Planning ADTP) Drganization : BRUHAT BANGALORE WAHANAGARA PALIKE Date : 05-Jan-2021 16: 53:07 COF TOWN PLANNING ( WEST	2020 bject val.	OWNER / GPA HOLDER'S SIGNATURE OWNER'S ADDRESS WITH ID NUMBER & CONTACT NUMBER : VANI S. KOWSHIK NO. 237, 1st A MAIN ROAD, WEST OF CHORD ROAD, 2nd STAGE, BASAVESHWARANAGAR, BANGALORE							
URU MAHANAGARA PALIKE		ARCHITECT/ENGINEER /SUPERVISOR 'S SIGNATURE KIRAN KUMAR DS No:338, Talakavery layout, Amruthahalli, Bangalore-92, Mob:9538654000 - 4400/0040 47					li,		
		PROJECT TITLE : PLAN SHOWING THE PROPOSED RESIDENTIAL BUILDING AT SITE NO. 237, WEST OF CHORD ROAD, 2nd STAGE, BASAVESHWARA NAGAR, BANGALORE, WARD NO. 67 (OLD NO. 14), PID NO : 14 - 74 - 237 DRAWING TITLE : 763641835-23-12-2020 09-56-13\$_\$VANI S KOWSHIK 2 :: A (A) with GF+2UF						A	
	-	SHEET	NO :	1					

Color Notes

SCALE : 1:100

This is system generated report and does not require any signature. Accuracy of Scrutiny Report and Drawing is subject to accuracy of end-user provided data, 3rd party software/hardware/services, etc. We are not liable for any damages which may arise from use, or inability to use the Application.