
SCALE: 1:100



B₹

PRODUCED

**ELEVATION** 

UserDefinedMetric (700.00 x 594.00MM)

31. Sufficient two wheeler parking shall be provided as per requirement. 32. Traffic Management Plan shall be obtained from Traffic Management Consultant for all high rise This Plan Sanction is issued subject to the following conditions: structures which shall be got approved from the Competent Authority if necessary. 33. The Owner / Association of high-rise building shall obtain clearance certificate from Karnataka Fire and Emergency Department every Two years with due inspection by the department regarding working a). Consisting of 'Block - AA (BB) Wing - AA-1 (BB) Consisting of STILT, GF+2UF'. condition of Fire Safety Measures installed. The certificate should be produced to the Corporation 2. The sanction is accorded for Plotted Resi development AA (BB) only. The use of the building shall and shall get the renewal of the permission issued once in Two years. 34. The Owner / Association of high-rise building shall get the building inspected by empaneled 3.Car Parking reserved in the plan should not be converted for any other purpose. agencies of the Karnataka Fire and Emergency Department to ensure that the equipment's installed are 4.Development charges towards increasing the capacity of water supply, sanitary and power main in good and workable condition, and an affidavit to that effect shall be submitted to the has to be paid to BWSSB and BESCOM if any. Corporation and Fire Force Department every year 5. Necessary ducts for running telephone cables, cubicles at ground level for postal services & space 35. The Owner / Association of high-rise building shall obtain clearance certificate from the Electrical for dumping garbage within the premises shall be provided. Inspectorate every Two years with due inspection by the Department regarding working condition of 6. The applicant shall construct temporary toilets for the use of construction workers and it should be Electrical installation / Lifts etc., The certificate should be produced to the BBMP and shall get the demolished after the construction. renewal of the permission issued that once in Two years. 7. The applicant shall INSURE all workmen involved in the construction work against any accident 36. The Owner / Association of the high-rise building shall conduct two mock - trials in the building / untoward incidents arising during the time of construction. , one before the onset of summer and another during the summer and assure complete safety in respect of 8. The applicant shall not stock any building materials / debris on footpath or on roads or on drains. fire hazards. 37. The Builder / Contractor / Professional responsible for supervision of work shall not shall not The debris shall be removed and transported to near by dumping yard. 9. The applicant / builder is prohibited from selling the setback area / open spaces and the common materially and structurally deviate the construction from the sanctioned plan, without previous approval of the authority. They shall explain to the owner s about the risk involved in contravention facility areas, which shall be accessible to all the tenants and occupants. of the provisions of the Act, Rules, Bye-laws, Zoning Regulations, Standing Orders and Policy Orders of 10. The applicant shall provide a space for locating the distribution transformers & associated equipment as per K.E.R.C (Es& D) code leaving 3.00 mts. from the building within the premises. 11. The applicant shall provide a separate room preferably 4.50 x 3.65 m in the basement for 38. The construction or reconstruction of a building shall be commenced within a period of two (2) installation of telecom equipment and also to make provisions for telecom services as per Bye-law No. years from date of issue of licence. Before the expiry of two years, the Owner / Developer shall give intimation to BBMP (Sanctioning Authority) of the intention to start work in the form prescribed in Schedule VI. Further, the Owner / Developer shall give intimation on completion of the foundation or 12. The applicant shall maintain during construction such barricading as considered necessary to footing of walls / columns of the foundation. Otherwise the plan sanction deemed cancelled. 39.In case of Development plan, Parks and Open Spaces area and Surface Parking area shall be prevent dust, debris & other materials endangering the safety of people / structures etc. in earmarked and reserved as per Development Plan issued by the Bangalore Development Authority. 13.Permission shall be obtained from forest department for cutting trees before the commencement

40.All other conditions and conditions mentioned in the work order issued by the Bangalore Development Authority while approving the Development Plan for the project should be strictly 14.License and approved plans shall be posted in a conspicuous place of the licensed premises. The building license and the copies of sanctioned plans with specifications shall be mounted on 41. The Applicant / Owner / Developer shall abide by the collection of solid waste and its segregation a frame and displayed and they shall be made available during inspections. as per solid waste management bye-law 2016. 15.If any owner / builder contravenes the provisions of Building Bye-laws and rules in force, the 42. The applicant/owner/developer shall abide by sustainable construction and demolition waste Architect / Engineer / Supervisor will be informed by the Authority in the first instance, warned in management as per solid waste management bye-law 2016.

43. The Applicant / Owners / Developers shall make necessary provision to charge electrical 44. The Applicant / Owner / Developer shall plant one tree for a) sites measuring 180 Sqm up to 240 Sqm b) minimum of two trees for sites measuring with more than 240 Sqm. c) One tree for every 240 Sq.m of the FAR area as part thereof in case of Apartment / group housing / multi-dwelling

unit/development plan. 45.In case of any false information, misrepresentation of facts, or pending court cases, the plan sanction is deemed cancelled. 46.Also see, building licence for special conditions, if any.

(Hosadaagi Hoodike) Letter No. LD/95/LET/2013, dated: 01-04-2013 :

Special Condition as per Labour Department of Government of Karnataka vide ADDENDUM

Applicant / Builder / Owner / Contractor and the construction workers working in the construction site with the "Karnataka Building and Other Construction workers Welfare Board"should be strictly adhered to

2.The Applicant / Builder / Owner / Contractor should submit the Registration of establishment and list of construction workers engaged at the time of issue of Commencement Certificate. A copy of the same shall also be submitted to the concerned local Engineer in order to inspect the establishment and ensure the registration of establishment and workers working at construction site or work place. 3. The Applicant / Builder / Owner / Contractor shall also inform the changes if any of the list of workers engaged by him.

4.At any point of time No Applicant / Builder / Owner / Contractor shall engage a construction worker in his site or work place who is not registered with the "Karnataka Building and Other Construction workers Welfare Board".

Total FAR Area

0.00

63.74

51.92

56.83

0.00

172.49

172.49

NOS

07

06

02

NOS

05

18

0

(Sq.mt.)

Area (Sg.mt.)

Resi.

0.00

63.74

51.92

56.83

172.49

172.49

HEIGHT

2.10

2.10

2.10

HEIGHT

2.00

116.50

0.00

167.77

Name UnitBUA Type UnitBUA Area | Carpet Area | No. of Rooms | No. of Tenement

116.50

0.00

167.77

Tnmt (No.)

00

01

02

Block :AA (BB)

Terrace Floor

Second Floor

Ground Floor

Total Number of Same Blocks

BLOCK NAME

AA (BB)

AA (BB)

AA (BB)

AA (BB)

AA (BB)

GROUND

SECOND

FLOOR PLAN

FLOOR PLAN FIRST FLOOR

R C C ROOF

**SECTION @ X-X** 

BLOCK NAME

SCHEDULE OF JOINERY:

SCHEDULE OF JOINERY:

UnitBUA Table for Block :AA (BB)

SPLIT 1

SPLIT 2

SPLIT 2

First Floor

Stilt Floor

Total:

Area (Sq.mt.)

10.37

69.40

69.40

69.40

287.98

D2

D1

ED

NAME

287.98

Deductions (Area in Sq.mt.)

Parking

0.00

0.00

0.00

0.00

64.06

64.06

64.06

StairCase

10.37

5.66

17.48

12.58

51.43

51.43

LENGTH

0.76

0.90

1.06

LENGTH

1.00

Floor Name

1.Accommodation shall be provided for setting up of schools for imparting education to the children o f construction workers in the labour camps / construction sites.

2.List of children of workers shall be furnished by the builder / contractor to the Labour Department 3. Employment of child labour in the construction activities strictly prohibited.

4. Obtaining NOC from the Labour Department before commencing the construction work is a must. 5.BBMP will not be responsible for any dispute that may arise in respect of property in question. 6.In case if the documents submitted in respect of property in question is found to be false or

fabricated, the plan sanctioned stands cancelled automatically and legal action will be initiated.

PROPOSED WORK (COVERAGE AREA) EXISTING (To be retained) EXISTING (To be demolished) AREA STATEMENT (BBMP) VERSION NO.: 1.0.4 VERSION DATE: 31/08/2021 PROJECT DETAIL: Authority: BBMP Plot Use: Residential Inward\_No: PRJ/5983/21-22 Plot SubUse: Plotted Resi development Application Type: Suvarna Parvangi Land Use Zone: Residential (Main) Proposal Type: Building Permission Plot/Sub Plot No,: SITE NO-07 Nature of Sanction: NEW City Survey No.: SITE NO-07 Location: RING-II PID No. (As per Khata Extract): PID NO-4-63-7 Building Line Specified as per Z.R: NA Locality / Street of the property: SITE NO-07,4th MAIN ROAD,M.S.R Zone: West

NAGAR, MATHIKERE, BANGALORE, WARD NO-35(OLD NO-4), PID NO-4-63-7 Ward: Ward-035 Planning District: 215-Mathikere AREA DETAILS: SQ.MT. AREA OF PLOT (Minimum) 111.42 NET AREA OF PLOT 111.42 COVERAGE CHECK Permissible Coverage area (75.00 %) 83.56 Proposed Coverage Area (62.29 %) 69.40 Achieved Net coverage area (62.29 %) 69.40 Balance coverage area left (12.71 %) FAR CHECK Permissible F.A.R. as per zoning regulation 2015 ( 1.75 ) Additional F.A.R within Ring I and II ( for amalgamated plot - ) Allowable TDR Area (60% of Perm.FAR)

Premium FAR for Plot within Impact Zone ( - ) Total Perm. FAR area ( 1.75 ) Residential FAR (100.00%) Proposed FAR Area Achieved Net FAR Area (1.55) Balance FAR Area ( 0.20 ) BUILT UP AREA CHECK Proposed BuiltUp Area

Approval Date:

Achieved BuiltUp Area

Color Notes

**COLOR INDEX** 

PLOT BOUNDARY ABUTTING ROAD

FAR &Tenement Details

Deductions (Area in Sq.mt.) Total FAR Total Built Up Tnmt (No.) Area (Sq.mt.) (Sq.mt.) Area (Sq.mt.) StairCase | Parking Resi. 172.49 51.43 64.06 287.98 172.49 Grand Total: 172.49 287.98 51.43 64.06 172.49 2.00

Block USE/SUBUSE Details Block Name Block Land Use Block SubUse Block Structure Category AA (BB) Plotted Res Bldg upto 11.5 mt. Ht. Residential

equired	Parking(Table 7a)	
equirea	Parking(Table ra)	

Required	raikiiiy( i a	ibie raj						
Block	Туре	SubUse	Area (Sq.mt.)	Units		Car		
Name		Subose		Reqd.	Prop.	Reqd./Unit	Reqd.	Prop.
AA (BB)	Residential	Plotted Resi development	50 - 225	1		1	2	-
_	<b>+</b> · ·			_	_		•	

## Parking Check (Table 7b)

Vehicle Type	I	Reqd.	Achieved		
	No.	Area (Sq.mt.)	No.	Area (Sq.mt.)	
Car	2	27.50	2	27.50	
Total Car	2	27.50	2	27.50	
TwoWheeler	-	13.75	0	0.00	
Other Parking	-	-	-	36.56	
Total		41.25	64.0		

OWNER / GPA HOLDER'S SIGNATURE

OWNER'S ADDRESS WITH ID NUMBER & CONTACT NUMBER Sri.ANAND.V.M NO-1-739,UPPER LINE,STATION BAZAR, GULBARGA, GBRS, KARNATAKA 505400

ARCHITECT/ENGINEER /SUPERVISOR 'S SIGNATURF Yatish N #12, 5th Cross, Brindavan Nagar, SBM colony(80 feet road), J.P. Park road, Near Chowdeshwari Bus stand, Mathikere, Bangalore-54


BCC/B.L-3.6/SE-241/2017-18 THE PLAN OF THE PROPOSED RESIDENTIAL BUILDING ATSITE NO-07,4th MAIN ROAD,M.S.R NAGAR,MATHIKERE,BANGALORE,WARD

NO-35(OLD NO-4), PID NO-4-63-7.

DRAWING TITLE 429319134-13-10-202110-30-39\$\_\$ANAND V M 30X40 SGFS 2K

This approval of Building plan/ Modified plan is valid for two years from the

SHEET NO: 1



This is system generated report and does not require any signature.